

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 167 — 21,447
County Number

Operator

Crude Producers, Inc.

Address

P.O. Box 55 Russell, Kansas 67665

Well No.

#1

Lease Name

Sander

Footage Location

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

Revlin Drilg., Inc.

Geologist

Glenn D. Tracy

Spud Date

5-19-80

Date Completed

5-24-80

Total Depth

3270'

P.B.T.D.

Directional Deviation

Oil and/or Gas Purchaser


State Geological Survey
WICHITA, BRANCH

copy

S. 9 T. 14 R. 15W E W

Loc. NE NW NE

County Russell

640 Acres
N

Locate well correctly

Elev.: Gr.

DF KB 1870'

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	28#	218	Quick-Set	150	
Production	7 7/8	5 1/2	14#	3274'	60-40 Poz Mix	300	4% Gilsomite 2% Gel 10% Salt 3/4 of 1% CFR2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at
2 7/8	3200	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production <i>July 1980</i>		Producing method (flowing, <u>pumping</u> , gas lift, etc.)			
DATE OF PRODUCTION PER 24 HOURS	Oil <i>8</i> bbls.	Gas MCF	Water	Gas-oil ratio bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

No other info Released

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Crude Producers, Inc.		DESIGNATE TYPE OF COMPLETION: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. #1	Lease Name Sander	Oil	
S <u>9</u> T <u>14</u> R <u>15</u> ^E W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Shale & Post Rock & Sand	0	20	R.T.D.
Post Rock-Shale	20	50	
Shale-Sand	50	220	
Shale	220	845	
Shale	845	898	
Anhyrite	898	939	
Shale & Red Clay	939	1320	
Shale & Lime Sections	1320	1745	
Shale w/Lime	1745	2040	
Lime - Shale	2040	2290	
Shale-Lime	2290	2590	
Shale w/Lime	2590	2830	
Lime	2830	2970	
Lime	2970	3090	
K.C.	3090		
Lime Stone	3090	3128	
Lime-Arbuckle	3128	3235	
Lime-Granite	3235	3270	
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	<i>Paula J. Gibson</i> _____ Signature Bookkeeper, Revlin Drilling, Inc. _____ Title May 27, 1980 _____ Date		