

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank, Wichita, Kansas.

SKELLY OIL CO.
Alex Dumler No. 2

SEC. 1 T. 14 R. 15W
SE SW NE
330' fr SL 990' fr WL. NE $\frac{1}{4}$

County Russell.

Total Depth. 2775 $\frac{1}{2}$
Comm. 1-23-37 Comp. 2-17-37
Shot or Treated. 2000 gal 2772-2775 $\frac{1}{2}$
Contractor. Triangle Drlg.
Issued. 4-10-37 Rotary 2774'
Cable 2775 $\frac{1}{2}$

CASING.

13" 463'
65/8" 2772



Elevation
Production. Pot. 1801 B.
(Pumped in 32)

Figures Indicate Bottom of Formations.

surface soil and clay	60
shells	80
shale and shells	101
sticky shale and shells	335
sand shale and shells	470
shale and shells	515
sd lime and shells	600
shale sand rock and shells	745
shale and shells	830
red bed	870
shale and shells	905
anhydrite	960
shale and lime shells	1025
red bed	1100
shale	1120
shale and shells	1590
lime with streaks of shale	1665
lime	2060
shale and lime	2080
lime	2175
shale red and lime	2200
lime and shale	2215
lime	2245
lime and shale	2290
lime	2390
shale	2425
shale and lime	2475
sticky shale	2555
lime and shale	2590
lime	2613
pyrites shale and lime	2635
shale and lime	2675
shale lime and gravel	2685
shale and lime shells	2725
lime and shale	2762
cored 2762-2774 Rec. 10 $\frac{1}{2}$ '	2762 steel lined hole at depth 2750
	Top 8 $\frac{1}{2}$ ' dark shale
	Bot. 2' Grey porous cherty lime Sat.
	Top of Topeka lime 2772.
	reamed hole 2762-2772 and set and
	cemented 85/8 casing.

grey porous lime 2775 $\frac{1}{2}$ SLM
washed free oil and hole filled with oil
as follows. 250' in 15 Min. 350' in 30 Min.
500' in 1 Hr. 600' in 2 hrs. 2000' in
9 hours.
Total Depth.

Topeka lime 2772 Top.
oil 2772-2775 $\frac{1}{2}$ main body pay formation.