

WELL LOG BUREAU @ KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

SKELLY OIL COMPANY.
A. Dumler No. 4

SEC. 1 T. 14 R. 15W.
SW SE NE
330' fr S.L. 990' fr EL

Total Depth. 3323 P.B. 2765 County Russell.
Comm. 5-22-37 Comp. 7-25-37
Shot or Treated. 3000 gal. 2766-2772 3000 gal 2759-2765
Contractor. Triangle Drlg. Co. 6000 gal 2759-2765
Issued. 10-9-37

CASING. Rotary 2770
Cable 3323

13" 421'
85/8" 2766'
7" 3306'



Elevation.

Production. DRY.

Figures Indicate Bottom of Formations.

surface soil clay and sand rock	40	lime	3250
sand rock and shells	150	slate blue	3257
shale and shells	425	lime	3280
shale and shells	450	shale grey crystalline lime and dolomite	3285
pyrites of iron hard	465	lime grey and grey dolomite	3290
shale and shells	500	Top siliceous lime	3284
sand	530	Rainbow show Oil	3285-3290
red bed shale and shells	890	hard crystalline lime and dolomite with little sand	3294
anhydrite hard	935	cherty lime and sand	3298 no shows.
shale and shells	1590	cherty lime and sand trace of shale	3302 no shows.
lime	1997	sand little shale and chert	3306 no shows.
pyrite and iron	2000	sand soft brown	3307 1/2
lime	2335	porous and sat.	
broken lime	2370	bailed and tested 12 hours 1/2 0 per hr.	
lime and shale	2558		
SIC 2558 equals 2569			
lime and shale	2766		
lime brown	2768		
Top Topeka lime 2766			
cored 2768-2770 Rec 1 1/2" all grey cherty lime no water. no porosity or saturation.			
lime hard grey	2772	sand light brown with green shale	3309
lime grey	2852	lime grey and dolomite little chert	3310
lime hard brown	2862	slight oil stained. tested 3 hrs no increase hole caving badly.	
lime grey	2953		
SIC 2953-2955			
lime hard grey	2957 no show oil		
1 1/2" BWPBR 2955-2957		lime hard grey	3316
lime grey cherty lime no sat. or porosity.	2965		
lime grey cherty	2975	sdv lime	3321 no shows.
lime grey	2990	water sand	3323
slate and broken shells	3008	had 800' sulphur water in hole in 4 hours.	
lime	3040	Total Depth. P.B. 3316	
shale and shells	3057	P.B. 3005	
Top Lansing lime	3054	P.B. 2773	
lime hard	3058	P.B. 2765	
sdv shale soft	3065		
lime hard	3125		
slight show oil	3120-3125		
sdv lime dark	3135		
lime w hito	3147		
hole full water	3145-3147		
sdv lime hard	3155		
lime w hito hard	3161		
shale blue	3170		
lime hard white	3173		
lime hard grey	3180		
lime	3205 light show oil		
shale	3207		