

THE TEXAS CO.
A. Dumler No. 2

DEEPENING RECORD.

SEC. 1 T. 14 R. 15W
NE NW SE
Approx. 330' fr N 990' fr
WL in N2 SE4

Total Depth. 3305
Comm. 2-26-37 Comp. 4-1-37
Shot or Treated.
Contractor. Thayer Drlg. Co.
Issued. 2-7-42 Ca ble 0-3110'

County. Russell



CASING:
15 1/2" 320'
12 1/2" 560'
10 " 914'
8 5/8" 2425'
7 " 2746' UR 3049
5 1/2" liner 156'

Elevation.

Production. Pot. Pump 329
Bbls.

Figures Indicate Bottom of Formations.

clay yellow sft	40	brkn lime med	2050
shale blue & blk sft	210	lime white med	2065
sdv shale lgt sft	220	brkn lime mod white	2070
shale blue sft	230	lime & shells mod	2090
sand white sft HFW	255	lime white hrd	2110
shale blue sft	270	red rock sft	2115
sand white sft	305	lime white hrd	2160
shale blue sft	340	red rock sft	2170
sand white sft	380	lime white hrd	2220
shale & iron blue sft	385	shale lgt sft	2230
HFW		lime lgt hrd	2255
shale blue sft	400	shale blk sft	2260
sand brown sft	410	lime lgt hrd	2295
shale blue sft	450	shale & lime lgt sft	2315
iron hrd	455	lime hrd	2320
shale sft	460	shale sft	2325
shale & iron blue mod	475	lime lgt hrd	2355
shale blue sft	490	shale & shells mod	2370
shale & iron blue mod	500	lime lgt hrd	2405
sdv shale blue sft	520	shale & shells mod	2425
shale blue sft	540	shale blue sft	2485
lime white hrd	545	lime white hrd	2495
shale red sft	695	shale blue sft	2510
sand red sft	705	lime white hrd	2525
shale red sft	903	shale blue sft	2540
chal k white sft	907	brkn lime mod	2550
lime white hrd	945	shale blue sft	2570
red rock sft	1110	lime white hrd	2580
shale grey sft	1145	shale blue sft	2585
red rock sft	1200	lime white hrd	2595
shale blue sft	1240	shale blue sft	2600
lime & shells blue sft	1270	lime white hrd	2605
salt & shale blue sft	1350	brkn lime med	2615
salt white sft	1560	lime white hrd	2650
shale blue	1565	lime shells mod	2675
lime white hrd	1570	lime white hrd	2680
shale blue sft	1605	shale blue sft	2715
lime white hrd	1630	lime white hrd	3000
brkn lime med	1680	shale blue sft	3002
lime white hrd	1695	lime white hrd	3007
shale blue sft	1700	shale blue sft	3012
red rock sft	1705	lime white hrd	3016
lime white hrd	1715	shale blue sft	3020
shale blue sft	1725	lime white mod	3035
lime white hrd	1755	red rock sft	3044
shale blue sft	1760	lime brown hrd	3045
brkn lime med	1815	slate blue sft	3050
red rock sft	1845	lime brown hrd	3069
lime lgt hrd	1950	shale blue white	3075
brkn lime mod	1965	lime hrd blue	3092
red rock sft	1975	shale blue sft	3093
lime white hrd	1980	lime brown hrd	3110
brkn lime med	1985	Total Depth.	
shale & shells mod	2000		
lime hrd	2010		

Hole started filling with
oil from 3075-3088.

DEEPENING RECORD.

Comm. 11-9-41
Comp. 12-16-41

Prod. Pot. 454 B.
Depthograph.

5 1/2' 156' liner.

lime	3110-3115
shale	3118
lime	3190
shale	3193
lime	3198
shale	3200
lime	3223
shale	3225
conglomerate	3228
lime	3249
shale	3258
lime	3278
shale	3282
lime	3302
sand	3305

Total Depth.