

THE TEXAS CO.
A. Dunler No. 4.

SEC. 1 T. 14 R. 15W
NE 1/4 SE
330' fr N & EL


Total Depth. 2942'
Comm. 7-10-37 Comp. 8-4-37
Shot or Treated.
Contractor. Thayer Drlg. Co.
Issued. 8-21-37

County. Russell

Cable top to bottom.

CASING:

15 1/2"	320'	P
12 1/2"	607'	P
10 "	916'	P
8 5/8"	2526'	
7 "	2936'	



Elevation.

Production. Pot. 3048 B.

Figures Indicate Bottom of Formations.

cellar	10	Red rock	1835
clay yellow	30	lime white	1870
shale grey	40	lime grey	1915
shale drk	85	lime white	1960
shale blue (wtr 200)	180	red rock red	1970
sdv shale grey	200	lime grey	2040
sand white	240	lime white	2060
shale blk (GBW 240)	255	lime grey	2070
shale lgt	265	lime white	2090
sand lgt HFW	270	red rock red	2095
shale blue	295	lime white 1BW 2155	2155
red rock red	300	red rock red	2175
shale blue	310	lime white	2225
red rock red	320	red rock red	2240
shale blue	340	lime white	2260
sand grey	360	shale blue	2265
shale blue	410	lime white	2295
sand white	415	shale & shells blue	2320
2 BW 415		shale blue	2325
shale blue	470	lime white	2340
sand white	490	shale & shells grey	2405
shale blue	505	lime white	2420
sand red	525	shale blue	2450
shale blue	540	lime white	2460
red rock red	585	red rock red	2465
red sand	590	shale blue	2524
red rock red	690	lime white	2545
sand red 1/2 BW 690-705	705	shale blue	2575
red rock red	750	lime white	2590
sand red 6BW 750-785	785	shale blue	2600
red rock red	905	lime white	2630
chalk white	908	shale blue	2645
lime white	950	lime grey	2660
red rock red	1095	shale blue	2720
shale blue	1135	lime white	2760
red rock red	1180	lime shells & shale	2775
shale blue	1275	lime white	2942
shale & salt blue	1320	Total Depth.	
salt grey	1370		
salt white	1595	Oil 2935-2940	
lime white	1600		
lime grey	1610		
lime blk	1620	Pot. 3048 B. This test was	
lime white	1665	natural and did not show any	
lime grey	1675	water.	
lime white	1690		
shale blue	1695		
lime white	1700		
red rock red	1710		
lime white	1735		
lime grey	1770		
lime white	1805		