

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- TEXAS CO.
Farm- C. Anschutz

No. 11

SEC. 1 T. 14 R. 15W
CEL E 1/2 SW

Total Depth. 3383

Comm. 11-7-51


Shot or Treated.

Contractor. Anschutz Drlg. Co.

Issued. 1-5-52

Comp. 12-9-51

County Russell
KANSAS



Elevation. 1868 KB

Production. SWDW

CASING:

10 3/4" 904' cem w/425 sxs.
7" 3320' cem w/108 sxs.

Figures Indicate Bottom of Formations.

shale	400
sand, shale	580
shale, red rock	665
red bed, shale, shells	755
red bed, sand strks	845
red bed	895
anhydrite	945
shale, salt	1030
red bed, shale, shells	1150
shale, shells	1400
shale, shells	1640
lime, shale	1740
lime, shale strks	1855
lime, shale	2015
shale, shells	2310
lime, shale	2355
shale, shells	2400
lime, shale	2495
lime	2500
lime, shale	3140
lime	3322
sand	3349
sand, shale	3368
granit wash, sand	3375
granite	3383
Total depth	

Tops:

Topoka	2754
Huebner	2981
Lansing	3035
Lower Reggin	3287
Granite	3368

12-9-51 Took input test at rate
of 4 barrels per minute for 1 1/2
hrs., no pressure, took 20 bbls.
in 8 minutes, on 15" vacuum
Injection formation lower Reggin.