

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.


GULF OIL CORP.
H. H. Pierce No. 2

SEG. 2 T. 14 R. 15W
NE NW SE

County. Russell

Total Depth. 3311'
Comm. 3-15-36 Comp. 5-16-36
Shot or Treated. 1000 Gals. Acid. 4-14-36
Contractor.
Issued. 9-5-36

CASING:
15 1/2" 285'
12 1/2" 547' Pulled
10 925' "
8 5/8" 2575' "
7 3061'
5 3/16" 3311'
5 3/16" liner 93' set 3122' Pulled.



Elevation.

Production. Pot. 2081 B.

Figures Indicate Bottom of Formations.

No water.

shale blue	200	lime	1845	shale	3130
shale grey	240	shale blue	1850	lime	3149
mud yellow	255	lime	1860	shale	3160
shale blue	285	shale blue	1885	lime	3187
pink rock	315	lime	1895	shale	3190
shale blue	355	shale blue	1900	lime	3194
sand	380	lime	2000	sand	3198
shale blue	400	slate shells	2060	lime	3232
sand	410	red rock	2070	red rock	3238
shale blue	455	lime	2085	shale brown	3243
water sand	465	shale	2095	shale	3244
mud blue	485	lime	2115	lime	3260
shale blue	500	lime brkn	2155	lime shells & shale	3275
lime	515	red rock	2175	lime	3280
shale blue	535	lime brkn	2335	shale	3284
shale brown	547	shale blue	2340	lime	3298
red rock	915	lime	2355	shale	3300
lime	925	shale drk	2405	lime	3302
anhydrite	955	brkn lime	2440	shale green	3310
lime	960	lime	2455	sand	3311
shale blue	965	shale blue	2480	Total Depth	
red rock	1120	lime	2500		
shale blue	1155	shale	2517	Gorham sand	3310-3311
red rock	1195	lime	2545		
lime shells	1215	shale	2570		
shale blue	1265	lime	2610	Acidized 4-14-36 with 1000	
lime	1280	shale blue	2620	Gallons 50% solution.	
shale blue	1305	lime	2650	Retest with permanent pump-	
salt	1600	shale blue	2710	ing equipment, 6-12-36	
lime	1615	lime	2755	potential 2283 Oil, 21 wtr.	
shale grey	1640	shale blue	2770		
lime	1670	lime	2995		
shale blue	1685	shale blue	3005		
lime	1700	lime	3027		
red rock	1720	various colored shale	3051		
lime	1750	lime	3071		
shale	1760	shale	3072		
red rock	1770	lime	3076		
lime	1815	shale	3081		
red rock	1840	lime	3122		