


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

STANOLIND OIL & GAS CO.
J.H. Dortland No. 10

SEC. 5 T. 14 R. 15W.
SW NE SE
1650' N of S.L. 1650' E
of W.L.

Total Depth, 3079
Comm. 10-27-37 Comp. 11-18-37
Shot or Treated.
Contractor.
Issued. 1-8-38

County Russell



CASING.

16" 40' 7" 3052

Elevation.

Production. Pot. 161 B.

Figures Indicate Bottom of Formations.

cellar soil	10	red rock	2115
clay	20	lime	2165
sdv shale	30	red rock	2190
shale	45	shale	2225
shale blue	185	lime	2235
sand	195	shale	2270
shale light	215	lime	2315
shale	240	shale blue	2320
sand HFW	255	shale	2375
shale	270	shale blue	2420
red rock	275	shale and shells	2465
shale	295	shale	2520
sand	315	lime	2538
shale blue	415	shale blue	2545
shale	445	shale and shells	2605
sdv shale	455	lime	2635
shale blue	465	shale	2645
sand	510	lime	2665
shale blue	525	shale Hole caving.	2675
red sand and shale	545	shale and shells	2740
red rock	920	lime	2765
anhydrite lime	925	shale soft blk	2775
lime	965	Topeka lime	2800
red rock	1100	show of oil and gas	2775 to 2782
shale blue	1160	lime	3008
red rock	1215	shale blue	3015
shale blue	1225	red rock	3018
red rock	1240	lime	3033
shale blue	1290	Variegated shale	3045
salt	1590	shale and shells	3050
shale blue	1605	Oswald lime	3054
lime	1650	S.L. corr. 3054 equals	3052
shale blue	1660	Top Oswald lime	3048
lime	1680	lime	3061
shale grey	1690	shale	3065
lime	1700	lime	3067
shale	1710	shale cored	3070
red rock	1725	lime hard cored	3071
lime	1755	shale blue cored	3074
shale blue	1775	lime hard cored	3076
lime	1825	lime soft cored	3079
red rock	1850	show of oil	3076-79
lime	1875		
shale grey	1885	Total Depth.	
lime	1965		
red rock	1975	Oswald lime	3048-3079
lime	2040		
shale	2050	1st 4 hours test pumped	27 oil 125 wtr.
lime	2070	2nd 4 hours test pumped	35 oil 109 wtr.
red rock	2080		
shale blue	2100		