

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - STANOLING OIL & GAS CO.
Farm - J. H. Dortlane "D" No. 12

SEC. 5 T. 14 R. 15W
SW NE SW
330' NS1 & 330' E1 SW $\frac{1}{4}$

Total Depth. 3280'
Comm. 7-10-48 Comp. 7-27-48
Shot or Treated.
Contractor.
Issued. 8-21-48

County. Russell

KANSAS



Elevation. _____

Production. Dry

CASING:
13" OD 154' Cem. W/200 Sx.

Figures Indicate Bottom of Formations.

post rock clay	90
shale shells pyrite	154
shale blue	200
red rock	285
sand	340
shale sdy shells	475
sand red	585
sand	920
lime	955
red bed shale	1130
shale shells	1280
redbeds & shale	1600
shale & shells	1837
shale & lime	1870
lime	1950
Top Tarkio	2742
Top Howard	2763
Top Topeka	2992
Top Hueber	3012
Top Dodge	3042
Top Lansing	3275
conglomerate	3280
Total Depth	

Crdr 3275 - 3277 No rec.
Crdr 3277 - 3280 Rec, 2'
of granite

Drld. 3070 - 3095 F. POR sli sat.
BST 3070 - 3095 Packer set 3068
tool open 1 hr. Red, 30' muc W/
scum oil BPH 550 PS
DST 3213 - 3223 Packer set 3211
tool open 30 min. No blow Rec.
5' mud BPH zero Scattered staining
good porosity.