

WELL LOG BUREAU, KANSAS GEOLOGICAL SOCIETY
 UNION NATIONAL BANK BLDG., WICHITA, KANSAS

27767

CASING RECORD

LOCATION NE $\frac{1}{4}$ NW $\frac{1}{4}$ NE $\frac{1}{4}$

SEC 8 T 14 R 15W.

10" 2168 FARM Dortmund (Gorham Field) NO. 1 COUNTY Russell
 20" 8 1-4 2748 COMPANY Keys Petroleum Corp
 15 1-2 450 6 5-8 3025 CONTRACTOR
 12 1-2 915 5 3-16 COMMENCED 12-1-26 COMPLETED 4-1-27



TOTAL DEPTH 3057 SHOT QUARTS BETWEEN
 CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO Keys Petroleum Corp.

Wakeeney, Kansas.,

ELEVATION

FIGURES INDICATE BOTTOM OF FORMATIONS.

INITIAL PRODUCTION 15bbls.

REMARKS

7-16-27.

24 hours.

FORMATION	DEPTH	FORMATION	DEPTH	FORMATION	DEPTH.
SHALE	155	shale blue	1915	lime	3008
sand	195	lime	1925	variegated shale	3024
red shale	225	brown shale	1950	lime Top of Oswald	
blue shale	250	lime	1960	SLM	3038
lime white	255	shale	1975	shale green	3045
brown sand	260	lime	2000	lime Oil	3057
lime hard	262	shale blue	2005		
blue shale	300	lime broken	2035	shot 40 qts 3045-3057	
sdv lime	325	shale blue	2050	bottom 3 joints 6" pipe	
blue shale	360	shale red	2060	collapsed Pulled 6"	
grey shale	375	lime broken	2065	and fished for 3 joints	
blue shale	395	shale blue	2070	pipe. Then tried to drill	
grey shale	400	brown shale	2080	out. Put in whipstock	
blue shale	425	shale	2095	cemented Drill hit 6"	
grey shale	450	brown shale	2100	bit lost in hole in	
grey sand	480	lime	2140	Dodge pay Adb.	
grey shale	505	shale red	2168		
sand white	540	lime	2220		
red rock	880	red rock	2230		
red sand	885	blue shale	2260		
red rock	911	lime	2270		
chalk	915	blue shale	2400		
lime	945	lime	2405		
red rock	950	shale	2445		
shale	960	lime	2450		
red rock	970	shale blue	2475		
shale light	980	shale sdv	2485		
red rock	1100	shale dark	2500		
shale light	1140	lime	2525		
red rock	1195	shale cave	2550		
shale blue	1205	lime	2556		
red shale	1220	shale cave	2580		
blue shale	1276	lime	2585		
salt	1547	shale	2600		
shale blue	1590	lime	2608		
lime	1595	shale	2620		
lime broken	1630	lime	2625		
shale blue	1665	shale	2685		
lime	1670	lime broken	2700		
shale	1685	shale light	2730		
red shale	1715	lime	2735		
lime and shale	1745	shale light	2748		
red shale	1750	show oil	2758		
blue shale	1775	lime	2880		
lime	1785	shale green	2887		
shale blue	1800	lime hard	2943		
shale red	1845	lime	2978		
lime and shale	1865	water	2943		
shale light	1870	shale green	2983		
lime hard	1880	lime	2988		
shale light	1885	shale blk	2994		
lime	1900	lime Dodge	3004		