


ALVA BILLINGS.
Witt No. 23.

SEC. 3 T. 14 R. 15W
NE SW SW

Total Depth. 3313'
Comm. 6-23-36 Comp. 7-19-36
Shot or Treated.
Contractor. Braden-McClure Drlg. Co.
Issued. 8-8-36

County. Russell

CASING:
15 $\frac{1}{2}$ " 343'
12 $\frac{1}{2}$ " 606'
10" 906'
8 $\frac{1}{4}$ " 2493'
6 5/8" 3029'
5 3/16" 3245'



Elevation.

Production. Dry & Abnd.

Figures Indicate Bottom of Formations.

cellar	8	shale	2420
Post rock & clay	30	lime	2435
shale blue	45	shale	2493
lime broken	75	lime	2515
shale blue	150	shale	2540
sand	165	lime	2565
shale blue	185	shale blue	2575
1 BWPB 170'		shale & lime	2660
sand 5 BWPB	210	shale	2690
shale	240	lime $\frac{1}{2}$ BW	2695
sand HFW	260	shale & lime	2715
shale	350	lime	2745
sand	360	shale	2750
shale	430	lime	2980
sand hard	435	Sho oil	2865
shale	500	shale dark	2992
red rock	595	lime (Dodge)	3007
iron	600	red rock	3012
red rock	897	shale blue	3024
6 BWPB 790		lime Oswald	3045
3 BWPB 820		shale	3050
lime	945	lime	3095
red rock	1095	shale	3098
shale blue	1135	lime	3155
red rock	1190	5 BWPB 1/3 B. Oil	3107
shale	1245	shale	3160
shale & lime	1275	lime	3200
salt	1550	shale blue & red rock	3205
lime & shale	1570	lime	3220
lime	1600	red rock	3224
lime & shale breaks	1650	lime & shale	3240
lime	1785	lime	3245
Show oil & gas 1720		lime & shale	3260
red rock & shale	1795	lime	3265
lime	1850	shale & red rock	3273
shale	1860	lime	3279
lime	1930	granite wash	3285
$\frac{1}{2}$ BWPB 1920		shale	3289
lime & shale	2005	granite wash	3313
lime	2045	Total Depth	
shale break	2055		
lime	2130		
red rock	2140		
lime	2205		
shale blue	2210		
lime & shale	2265		
shale	2270		
lime	2320		
shale	2330		
lime	2345		
shale	2355		
lime	2360		
shale blue	2370		
lime	2410		

Plugged & abandoned July 21, 1936