

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

A. H. WITT
Joe Furthmyer No. 2.

SEC. 9 T. 14 R. 15 W
CE $\frac{1}{2}$ SE SE

Total Depth. 3024 Corr. to 3030'
Comm. 12-8-42 Comp. 1-8-43
Shot or Treated. 3000 Gals.
Contractor.
Issued, 3-20-43

County. Russell



CASING:

20" 18'3" 8" 2341'5" Reamed
15 $\frac{1}{2}$ " 387' to 2459'5" P
12 $\frac{1}{2}$ " 580' 7" 2996'5"
10" 893'

Elevation.

Production. Pot. 470 B.

Figures Indicate Bottom of Formations.

cellar	9	shale blue	2510
clay sdy	20	lime	2535
shale blue	180	shale	2540
shale wh	200	lime	2550
red rock	260	shale	2570
shale blue	280	shells & shale	2695
sand	310	shale sft	2710
red rock	320	lime	2790
shale blue	430	shale blue	2794
sand HFW	445	brkn lime & shale brks	
shale blue	460	blue	2810
sand-more wtr	490	lime	2835
red rock sdy	565	shale	2840
redrock	665	lime	2850
shale sdy 2 $\frac{1}{2}$ BW	690	shale	2858
red rock	735	lime	2885
sand 4 BW	760	lime brkn $\frac{1}{2}$ BW	2905
red rock	865	shale & shells	2954
redrock & chalk	884	lime Dodge	2970
lime	918	Top of Dodge	2954
red rock	1065	sm sh oil&gas	2954-59
shale blue	1090	lime shells & shale	
red rock	1180	blue	2989
shale blue	1225	lime	3005
salt	1540	shale	3008
shale blue	1550	lime	3010
shale & shells	1660	brkn lime, sm sh oil	3016
red rock	1675	brkn lime, more oil	3020
lime	1700	lime hd	3024
shale	1740	Correction:	
lime	1750	Run Sun Oil Well Cement-	
shale blue	1765	ing Co. steel line	
red rock	1800	3024 corr. to read 3030	
lime	1815	Corr. on Top Dodge	
shale blue	1825	lime 2954-2963 corr.	
lime	1880	to read: Oil at 2963-68	
shale blue	1890	Hole filled 470' in	
lime	1910	16 hrs - bailer tube	
shale blue	1920	5" x 47'	
shale brown	1930	Total Depth	3030
lime	1985		
shale	2000		
lime	2020		
shale & shells	2045		
shale brown	2055		
shale & shells	2070		
lime	2080		
shale blue	2090		
lime	2114		
red rock	2130		
lime	2155		
red rock	2160		
lime	2180		
shale brown	2200		
lime	2240		
shale blue & lime			
shells	2460		
lime	2467		