

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
 Union National Bank Bldg, Wichita, Kansas.

BRIDGEPORT MACHINE CO.
 A.H. Witt No. 7


SEC. 3 T. 14 R. 15W.
 SE NW SW

Total Depth, 3112.
 Comm. 12-7-35 Comp. 1-9-36.
 Shot or Treated. 3000 gal acid.
 Contractor, Bridgeport Machine Co.
 Issued. 2-1-36.

County, Russell.

CASING.

15 $\frac{1}{2}$ "	400'	8 $\frac{1}{2}$ "	2525'
12 $\frac{1}{2}$ "	608'	6 $\frac{1}{2}$ "	3037'
10"	918'		



Elevation.

Production, 1168 B. Pot.

Figures Indicate Bottom of Formations.

cellar	10	shale red	1705	shale blue	2978
clay yellow	20	shale blue	1775	lime	2990
shale and clay	65	lime	1790	1 BW and sh of oil at	
shale blue	115	shale blue	1800	2955-2960	
shale dark	155	red rock	1815	shale	3004
sand	175	lime	1850	lime	3014
water 1B. 155-175		slate blue	1855	shale	3020
shale blue	195	lime	1865	red rock	3030
sand	220	slate blue	1880	shale blue	3035
4 BW 195-215		lime	1930	Oswald lime	3040
slate blue	245	red rock	1945	lime	3056
sand	255	lime	1955	shale	3058
water Hole full 255		shale blue	1970	lime sh oil	3060
slate grey	300	lime and sand	2005	lime hard	3073
sand	330	shale blue	2010	lime sh oil	3080
slay blue	370	shale brown	2025	19 B Mud&Muck. from	
iron	372	lime	2050	oil 3055-3060	
sand	380	slate	2065	lime	3112
slate	385	shale blue	2095	Total Depth,	
sand water	390	lime	2120	some pay 3104-3112	
slate blue	440	red rock	2155		
sand	455	lime	2180		
shale blue	470	slate blue	2215		
sand	505	lime	2235		
red rock	515	red rock	2250		
red rock	575	lime	2285		
sand	595	shale blue	2300		
red rock	755	lime	2315		
sand red	775	shale blue	2340		
10 BW 765		lime	2350		
red rock	850	shale blue	2430		
sand	860	red rock	2450		
red rock	900	shale brown	2470		
lime anhydrite	913	shale blue	2500		
lime	918	lime	2525		
lime	948	shale blue	2550		
red rock	1090	lime	2600		
shale blue	1125	lime	2610		
shale blue	1130	shale blue	2625		
red rock	1220	lime	2635		
shale blue	1280	shale blue	2670		
salt	1565	lime	2725		
shale blue	1575	shale	2740		
lime	1600	lime	2760		
broken lime	1640	shale blue	2775		
lime	1650	lime	2890		
slate blue	1685	lime	2975		