


J.C. SHAFFER, INC.
K. Polcyn No. 6

SEC. 10 T. 14 R. 15W.
NW SE NE

Total Depth. 3279
Comm. 10-11-36 Comp. 11-3-36
Shot or treated.
Contractor. J. C. Shaffer.
Issued. 2-13-37

County Russell



CASING.

10" 615' 7" 3255'

Elevation.

Figures Indicate Bottom of Formations.

Production. Pot. 434 B.
Retest 1574 B.

surface and sand	190	
surface	260	
clay shale and shells	410	
sand and shells	615	
red rock	710	
red rock	900	
anhydrite	918	
lime anhydrite	940	
red rock and shale	1095	
shale and shells	1130	
shale and salt	1360	
shale and shells	1595	
gypsum and shale	1695	
lime and shale	1885	
lime shells and shale	2035	
lime and sticky shale	2100	
lime and shale	2130	
shale and shells	2180	
shale and shells	2280	
lime and shale	2355	
shale and shells	2430	
shale and shells	2530	
lime and shale	2605	
shale and shells	2705	
shale and lime shells	2790	
lime and shale	2840	
lime hard	2845	
lime	2885	
broken lime	2920	
lime and shale	2985	
broken lime	3045	
lime and shale	3140	
lime	3170	
lime and shale	3240	
lime	3255	
shale	3260	
lime	3265	
sand	3269	I.P. 434 B.
SLC 3269 equals 3271		
sand	3279	
Total Depth.		