


J.C. SHAFFER, INC.
K. Polcyn No. 8

SEC 10 T. 14 R. 15W.
SE SE NE

Total Depth. 3255 $\frac{1}{2}$
Comm. 11-23-36 Comp. 12-16-36
Shot or Treated.
Contractor. J.C. Shaffer, Inc.
Issued. 3-6-37

County Russell.



CASING.

10" 614' 7" 3240'

Elevation.

Production. Pot. 805 B.

Figures Indicate Bottom of Formations.

sand and shells	600
lime shells and shale	614
shells and red rock	750
red rock and shale	875
lime	905
anhydrite	940
shale and shells	1110
shale and lime shells	1275
salt	1300
salt and shale	1510
shale and shells	1560
shale and lime shells	1675
shale and lime	1800
broken lime	1830
lime and shale	2070
shale and lime shells	2135
shale and lime	2520
shale, shells	2605
shale	2690
shale and lime	2770
lime shale and shells	2830
lime and shale	2955
lime	3015
lime and shale	3075
Top of Oswald 3020 show of oil	
lime and shale	3240
shale	3244
lime	3245
lime and shale	3254 (OIL SAND 3252)
Gorham sand	3255 $\frac{1}{2}$
Total Depth.	