

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

STANOLIND OIL & GAS CO.  
S.T. Mills No. 1.

SEC. 10 T. 14 R. 15W.  
NE NE SW  
2310' N of S.L.  
2310' E of W.L.

Total Depth. 3274  
Comm. 10-29-37 Comp. 12-17-37  
Shot or Treated.  
Contractor.  
Issued. 1-22-38

County. Russell.



CASING. CABLE

16" 40'  
7" 3270'

Elevation.

Production. Pot. 874 B.

Figures Indicate Bottom of Formations.

cellar soil	8	red rock	2210	shale	3097
sdv soil	20	shale grey	2215	lime 1 B.W.	3165
shale blue	60	lime	2225	shale	3172
shale soft dark	150	shale grey	2245	lime	3210
shale grey	220	lime	2275	S.L.C. 3210 = 3205	
shale red	250	shale blue	2280	lime	3230
sand HFW	320	lime	2295	shale	3240
shale pink	325	shale blue	2305	lime	3264
shale blue	410	lime	2325	shale oil at 3271	3271
shale	435	shale grey	2335	S.L.C. 3271 = 3270	
shale blue	450	lime	2340	Gorham sand	3272
sand	495	shale grey	2350	Gorham sand cored	3274
red rock	520	lime	2355		
shale red	523	shale grey	2375	Total Depth.	
shale blue	528	lime	2385	Gorham sand 3270-3274	
shale red	530	shale grey	2410		
red rock	555	lime	2430	1st 4 hours test pumped	
shale red HFW	645	shale blue	2490	168 bbls oil.	
red rock	690	lime	2495	2nd 4 hour test pumped	
shale red	740	shale grey	2500	146 bbls oil.	
red rock	825	lime	2505		
shale red	865	shale grey hole cav.	2540		
red rock	889	lime	2555		
Anhydrite lime	930	shale grey	2565		
shale red	965	lime & shale	2600		
red rock	1180	lime sholls and grey			
shale blue	1245	shale	2650		
shale grey	1275	shale grey	2685		
salt	1550	lime	2730		
shale blue	1560	shale grey	2738		
lime and shale	1595	lime	2873		
shale blue & lime	1650	shale grey	2875		
lime	1660	lime	2880		
shale grey	1670	shale grey	2883		
lime	1675	lime LBW	2965		
red rock	1685	shale grey	2969		
lime	1715	lime	2975		
shale grey	1725	shale grey	2980		
lime	1770	lime	2995		
red rock	1810	S.L.Corr. 2995 = 3005			
lime	1845	lime	3010		
shale white	1850	red rock	3020		
lime	1935	lime	3030		
red rock	1950	Oswald lime	3047		
lime	2000	shale blue	3050		
shale green	2010	S.L.Corr. 3050 = 3049			
shale blue	2015	shale Cored	3052		
lime	2055	lime cored	3055		
red rock	2065	3/4 B.W. small show oil at			
lime	2085	3053-3055			
shale and lime	2120	Hard Non-porous lime	3057		
lime	2125	Cored.			
red rock	2145	lime cored	3063		
lime 1/4 B.W.	2195	Porous lime cored	3065		
shale grey	2200	lime	3092		