


CENTRAL PETRO. CO.
Foster No. 5BX. (Twin to No. 5B.)

SEC. 3 T. 14 R. 15W
NE SE NE

Total Depth. 3304'
Comm. 9-24-37 Comp. 10-26-37
Shot or Treated.
Contractor. Harry Gore
Issued. 11-13-37

County. Russell



CASING:
15 1/2" 390'
12 1/2" 615'
10 " 932'
8 1/4" 2767'
6 5/8" 3094'
5 3/16" 3299'

Elevation.

Production. Pot. 2268 B.

Figures Indicate Bottom of Formations.

cellar	10	shale blue	2090	shale blue	3040
clay yellow	35	lime	2115	lime Oswald	3059
shale blue	80	shale blue	2125	shale blue	3065
shale drk	110	lime	2150	lime hrd	3066
shale blue	180	red rock	2165	lime sft	3070
shale lgt	235	lime	2195	lime hrd	3074
sand wtr	260	slate	2200	lime sft	3078
red rock	310	lime	2226	lime	3250
shale sdy	350	red rock	2235	shale blue	3260
sand	355	lime	2260	lime	3276
shale blue	410	shale blue	2268	shale blue	3284
sand wtr	420	lime	2305	lime	3289
shale blue	447	shale blue	2325	shale	3292
sand & iron	475	shale & shells	2360	lime	3294
shale blue	495	shale blue	2370	shale blue	3297
sand wtr	525	lime	2380	lime	3299
red rock	565	shale blue	2385	sand Gorham	3303
sand & iron	600	lime	2390	shale	3304
sand wtr	610	shale blue	2395	Total Depth.	
shale	615	lime	2410		
red rock	920	shale & shells	2425		
lime anhydrite	957	shale blue	2435		
red rock	1105	lime	2440	Dodge lime 3007-3023	
shale blue	1150	shale & shells	2465	Oswald lime 3040-3059	
red rock	1165	lime	2475	oil at 3066-70	
lime	1171	shly shale	2485	Gorham sand 3299-3303	
red rock	1200	shale blue	2505	pay	
shale blue	1270	lime	2520		
salt	1580	shale blue	2562		
shale blue	1590	lime	2580	Water Record	
lime	1596	shale blue	2585	HFW 235-250	
shale blue	1610	lime	2590	HFW 410-20	
lime brkn	1650	shale blue	2595	4 BW 690	
lime	1665	lime	2615	10 BW 780	
shale blue	1675	shale & shells	2625	4 BW 850-60	
lime	1685	lime	2630	1/2 BWPH 2165-2175	
shale blue	1695	shale blue	2640	3 BW 2475-85	
red rock	1705	lime	2648	HFW, some oil 3100- 3105	
lime	1740	shale blue	2680		
shale blue	1780	lime	2690		
lime	1785	shale blue	2700		
lime brkn	1810	lime	2705		
red rock	1835	slate blue	2715		
lime	1870	lime	2748		
shale blue	1875	shale blue	2764		
lime	1950	lime	2853		
red rock	1965	shale blue	2856		
lime	1990	lime	2897		
shale blue	1995	shale blue	2900		
lime	2015	lime	2960		
shale blue	2025	lime sft	2995		
shale & shells	2035	shale blue	3007		
red rock	2040	lime Dodge	3023		
lime	2070	shale brown	3030		