

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.  
412 Union National Bank Bldg, Wichita, Kansas.

CENTRAL PETRO. CO.  
W.T. Foster No. 11-B.


SEC. 3 T. 14 R. 15W.  
SW NE NE

Total Depth. 3315.  
Comm. 8-20-37 Comp. 9-20-37  
Shot or Treated.  
Contractor. Harry Gore.  
Issued. 10-30-37

County Russell.

CASING.

15 1/2" 395'  
12 1/2" 608'  
10" 940'  
8 1/4" 2538' Underdug to 2782  
65/8" 3080  
53/16" 3275 UR 3310



Elevation.

Production. Pot. 2268 B.

Figures Indicate Bottom of Formations.

cellar	10	lime	2180	shale blue	3220
clay yellow	35	red rock	2195	lime	3255
shale blue	65	limo	2245	shale blue	3260
sand dry	75	shale and shells	2255	lime	3266
shale grey	95	limo	2265	shale blue	3275
shale blue	175	shale blue	2270	lime	3286
shale light	200	limo	2285	shale blue	3292
shale blue	230	shale blue	2295	lime	3299
shale sdy	250	lime	2325	shale	3302
shale blue	290	shale and shells	2410	lime shell	3303
sand water	305	shale blue	2425	shale blue	3306
shale blue	335	lime	2445	lime broken	3310
sand water	345	shale and shells	2460	lime hard	3312
shale blue	355	shale blue	2476	oil sand	3314
sand and iron	370	lime	2480	shale green	3315
shale light	420	shale blue	2490	Total Depth.	
shale sdy	430	lime	2503		
shale blue	455	shale blue	2515		
sand water	480	lime	2545	20 BW 230-250	
shale blue	515	shale blue	2555	HFW 290-305	
sand water	525	lime	2565	3 BW 410-20	
red rock sdy	545	shale	2575	HFW 455-480	
sand and iron	580	shale and shells	2585	7 BW 750-60	
red rock iron	585	lime	2590	1/2 BWP 1870	
red rock	605	shale blue	2596	2 BW 2490-2503	
sand water	615	lime	2600	1 BW 2990-95	
red rock	927	shells and shale	2620		
lime anhydrite	972	lime	2638	Dodge lime 3020-3037	
red rock	1130	shale blue	2643	Oswald limo 3058-3076	
shale blue	1170	lime	2660	show oil 3080-85	
red rock	1210	shale	2665	Gorham sand 3312-3314	
shale blue	1290	lime	2670	Pay.	
salt	1620	shale blue	2680		
shale and shells	1660	lime	2685		
lime	1675	shale blue	2717		
slate	1690	lime	2745		
lime	1705	shale and limo	2770		
red rock	1715	shale	2779		
limo	1765	shale blue	2782		
red rock	1775	lime	2900		
lime	1805	shale and shells	2915		
lime broken	1825	lime	3005		
red rock	1840	shale and shells	3015		
lime	1965	shale blue	3020		
red rock	1975	lime (Dodge)	3037		
lime	2010	red rock	3045		
shale blue	2020	shale blue	3058		
limo	2040	limo Oswald	3076		
shale and shells	2085	shale blue	3080		
red rock	2095	lime	3095		
lime	2125	lime sdy	3104		
shale and shells	2140	lime	3215		