


CENTRAL PETRO.CO.
Foster No. 18-B.

SEC. 3 T. 14 R. 15W
CN $\frac{1}{2}$ NW NW

Total Depth. 3078'
Comm. 12-17-39 Comp. 1-19-40
Shot or Treated.
Contractor. Harry Gore
Issued. 2-17-40

County. Russell



CASING:
15 $\frac{1}{2}$ " 380'
12 $\frac{1}{2}$ " 615'
10 " 922'
8 $\frac{1}{4}$ " 2505' UR 2775'
6 5/8" 3050' UR 3063'
Corrected M & set at 3065'

Elevation.

Production. Pot. 720 B.

Figures Indicate Bottom of Formations.

cellar	10	shale blue	2685
clay	35	lime	2735
slate	170	shale blue	2745
shale sdy	225	lime	2750
slate	250	shale blue	2753
redrock	270	lime	2900
sand wtr	300	shale blue	2905
slate	365	lime	3000
sand wtr	375	shale blue	3008
shale blue	390	lime Dodge	3025
shale sdy	470	red rock	3030
shale blue	490	shale blue	3040
red rock sdy	565	lime Oswald	3045
red rock	585	slate	3050
sand wtr	605	lime	3055
red rock	911	shale wh	3058
lime anhydrite	953	lime	3078
red rock	1095	Total Depth.	
shale blue	1140		
red rock	1200		
shale blue	1280	sh oil 2745-50	
salt	1585	sh oil 2975-80 Oswald	
salt, shale & lime	1625	oil 3065-3075--Corrected M	
shale & shells	1660	oil 3067-77	
lime	1690		
red rock	1705	10BW 210-20	
lime	1740	HFW 270	
red rock	1750	3 BW 460-70	
lime	1800	HFW 500	
red rock	1810	3 BW 685	
lime	1945	HFW 808	
red rock	1955	1 BW 2950-60	
shale & shells	1990		
lime	2025		
shale blue	2035		
lime	2060		
red rock	2055		
lime	2090		
shale & shells	2140		
red rock	2155		
lime	2220		
shale wh	2230		
lime	2240		
shale blue	2250		
lime	2295		
shale & shells	2380		
lime	2405		
shale & shells	2425		
shale blue	2495		
lime	2510		
slate	2545		
lime	2582		
shale & shells	2600		
lime	2610		
shale blue	2615		
lime	2635		
shale blue	2645		
lime	2650		
shale & shells	2675		