

BRIDGEPORT MACHINE CO.
 Polcyn No. 1

SEC. 10 T. 14 R. 15W.
 NWc NE


DEEPENING RECORD

County. Russell.

Total Depth. 3285
 Comm. 6-8-35 Comp. 8-13-35
 Shot or Treated.
 Contraotor.
 Issued. 5-9-36

CASING.

15 1/2"	352'	8 1/2"	2520'	UR 2768
12 1/2"	610'	65/8"	3068	
10"	965'	5"	3180	



Elevation.

Production. 60 bbls 1st
 24 hours.

Figures Indicate Bottom of Formations.

cellar	11	red rock	2155	<u>DEEPENING RECORD</u>
clay yellow soft	21	lime	2165	Post 1050 Bbls
slate blue soft	160	shale red	2175	Comm. 3-6-36 Comp. 4-1
slate grey	180	shale grey	2185	Old T. D. 3105
sand soft 3 BW	190	lime grey	2195	lime 3105-3166
slate grey	235	shale W.	2225	red rock 3172
sand brown	250 HF	lime W.	2235	lime 3180
red mud	270	slate brown	2250	lime 3231
slate blue	285	lime	2255	lime & salt 3240
sand red	335	slate grey	2275	lime 3258
slate blue	345	lime	2295	shale blue 3268
slate blue very sticky	355	slate grey	2300	lime 3275
slate grey	380	lime grey	2302	lime & shale 3280
sand	395	shale white	2350	sand pay 3285
slate blue	475	slate blue soft	2385	Total Depth
sand soft	545	slate brown	2395	
slate brown	582	lime white	2405	
sand brown	595	slate grey	2450	
red rock	605	slate blue	2505	
shale blue	610	lime white	2515	
slate red soft	705	slate blue	2580	
sand 3 BWPBR	720	lime	2590	
slate red 7 BWPBR	770	slate blue soft	2625	
sand red	913	lime	2645	
lime anhydrite hard	955	slate blue	2700	
slate red soft	1120	lime	2705	
slate grey	1140	slate blue	2720	
slate red	1230	lime hard	2745	
slate grey	1280	shale blue	2760	
salt	1575	lime	2835	
slate blue soft	1600	shale blue	2845	
lime white	1615	lime	2880	
shale white	1640	slate blue	2900	
lime white	1648	lime	2930	
shale	1658	shale blue	2945	
lime grey	1670	lime	2980	
slate red	1705	shale blue	2985	
lime grey	1730	lime white hard	2990	
slate brown	1750	slate grey	2995	
lime broken	1785	shale	2998	
red rock	1820	lime	3012	
lime grey med	1825	red rock	3025	
slate grey med	1835	shale blue	3030	
lime grey med	1848	lime broken	3068	
slate red	1860	lime hard	3072	
lime white	1900	lime soft	3080	
shale	1910	lime hard	3097	
lime grey	1935	lime soft	3102 1/2	
slate grey	1945	lime soft	3105	
slate brown	1955	Total Depth.		
lime	1980	First oil 3072 to 3080		
shale	1985			
lime	2005	anhydrite	913	
shale brown	2025	show of oil 2750		
lime grey	2035	Big lime 2774		
shale grey	2055	show oil 2900		
lime grey	2065	show oil 2930-35		
slate brown	2100	Top Oswald 3030		
shale blue	2125	Pay 3055-71		
lime	2140	Pay 3096-99		

Low by Bureau