

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

A.H.WITT.
A.H.WITT No. 7

SEC. 3 T. 14 R. 15W.
SE NW SE

Total Depth. 3297
Comm. 5-23-40 Comp. 7-5-40
Shot or Treated.
Contractor.
Issued. 9-28-40

County Russell.

CASING.

20" 20' P 8 $\frac{1}{4}$ " 2590' P
15 $\frac{1}{2}$ " 360' P 7" 3055' reamed to 3296'7"
12 $\frac{3}{8}$ " 615' P
10" 925' P

Elevation.

Production. Pot. 131.75 B.

Figures Indicate Bottom of Formations.

derrick floor to bottom		lime	2025	7 B.O. and 1 $\frac{1}{2}$ BW 3130-43	
cellar	10	shale blue	2045	lime	3215
shale blue	185	lime	2080	shale brown	3220
shy shale	200	shale grey	2090	lime	3238
sand water	215	lime shale brakes	2125	lime sh oil	3247
shale blue	225	broken lime	2145	shale blue	3255
red rock	240	shale brown	2180	lime	3270
shale blue	245	lime	2190	showing oil 3255-3260	
sand water	275	shale blue	2205	shale blue	3275
red rock	280	lime	2215	lime & shale brks	3284
shale blue	295	shale blue & shells	2225	shale blue	3289
sand	345	lime	2255	shale & shells	3293
shale grey	395	shale blue shells	2260	shale	3294
sand 8 BW	410	lime	2295	lime	3295
shale blue	445	shale blue	2330	lime Oil	3297
sand HFW	465	lime	2335		
shale blue	490	lime shells and shale	2350	Total Depth.	
red sand	585	shale blue	2385	Top Anhydrite	920
sand	600	lime shells & shale			
shale red	710	brakes	2440		
sand 2 BW	720	shale grey	2465		
sand	735	lime light sh oil	2475		
red rock	775	shale blue	2497		
sand	920	lime	2520		
780-790 8 BW		shale blue	2565		
anhydrite	925	lime	2575		
lime	965	broken lime	2590		
red rock	1115	lime	2605		
shale blue	1150	shale blue	2610		
red rock	1205	lime	2625		
shale blue & shells	1290	shale blue	2633		
salt	1315	shale & shells	2675		
shale blue	1320	shale grey	2705		
salt	1575	lime	2720		
shale & shells	1590	shale blue	2730		
lime	1600	lime	2750		
shale blue	1610	shale blue	2765		
lime	1630	Topeka lime	2800		
shale grey	1640	small showing oil & gas	2765		
lime shells shale	1650	lime	2965		
lime hard	1660	lime	2993		
shale blue	1670	small sh oil 2965-2980			
lime	1682	shale blue	3005		
shale blue	1692	Dodge lime	3025		
lime pink	1712	shale blue	3030		
lime	1750	shale brown	3045		
lime shale shells	1770	shale	3046		
shale blue	1775	lime	3062		
lime	1800	shale blue	3069		
red rock	1820	lime	3072		
lime	1865	showing oil 3070-76			
shale blue	1870	lime	3130		
lime	1950	soft 3118-3125			
shale	1960	lime	3136		
lime	1990	showing oil & gas 3130-3136			
lime shale shells	2000	about $\frac{1}{2}$ B.O. and $\frac{1}{2}$ BW 3136-3143			
shale blue	2005	lime	3164	About $\frac{1}{2}$ B.O. Some water.	