

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
 Union National Bank Bldg, Wichita, Kansas.

CENTRAL PETROLEUM CO.
 Dortland No. 2-D

SEC. 4 T. 14 R. 15W.
 SEC 1W

Total Depth. 3061
 Comm. 3-15-35 Comp. 4-14-35
 Shot or Treated.
 Contractor. Harry Gore.
 Issued. 5-4-35

County. Russell.

CASING.

12 $\frac{1}{2}$ " 603' 65/8" 3024'
 10" 910
 8 $\frac{1}{2}$ " 2523
 reamed to 2765-7



Elevation.

Production. 1024 B.

Figures Indicate Bottom of Formations.

soil brown	8	red rock	2070
sand brown	18	shale lime shells	2130
shale blue	150	shale red	2155
shale grey	190	lime and shells	2165
sand	215	lime	2195
shale	225	shale grey	2205
shale brown	250	red rock	2215
shale white	310	lime	2225
shale blue	350	lime shells	2250
shale white	370	lime	2275
shale grey	390	shale blue	2280
shale blue	415	lime and shells	2350
shale grey	425	shale grey	2375
sd shale	440	lime	2380
shale grey	480	shale blue	2405
sand grey	525	lime	2410
red rock	585	shale blue	2420
sand red	595	red rock	2425
red rock	895	shale grey	2435
lime grey	940	lime	2440
red rock	965	shale	2488
red rock	980	lime	2500
shale blue	1000	shale blue	2510
red rock	1105	shale blue	2523
shale blue	1135	shale dark	2545
red rock	1195	slate blue	2550
shale brown	1210	lime	2565
shale blue	1235	shale grey	2584
salt	1550	lime	2605
shale blue	1565	shale grey	2620
lime	1585	lime	2630
shale grey	1600	shale grey	2650
lime	1660	lime	2655
slate white	1670	shale grey	2725
lime	1675	slate	2755
red rock	1695	lime	2977
lime	1700	shale	2982
slate blue	1725	lime	3000
shale grey	1750	shale grey	3007
lime	1790	red rock	3012
shale red	1820	shale	3023
lime hard	1845	lime Oswald	3024
slate white	1850	lime	3036
lime	1935	shale blue	3041
shale grey	1940	lime Oil pay	3053
red rock	1945	lime	3061
lime	1975		
slate white	1980	Total Depth.	
lime	2005	HFV 275	
shale blue	2015	10 BW 430-440	
lime	2040	HFV 785-800	
shale blue	2045	showing of oil and water 2940	
lime	2055		
shale grey	2065	Oswald 3024-3061	Pay