

STANOLIND O. G.
C.A. Mermis No. 24. 7

SEC. 5 T. 14 R. 15W
SW SE NE
330' N 990' W SE NE $\frac{1}{4}$

Total Depth. 3075'
Comm. 5-26-37 Comp. 7-16-37
Shot or Treated.
Contractor.
Issued. 8-21-37 CABLE

County. Russell



Elevation.

CASING:
16" 43'
13" 567'
10 3/4" 926'
8 5/8" 2740'
7 " 3040'

Production. Pot. 506 B.
2 BW last 8 hrs.

Figures Indicate Bottom of Formations.

shale	45	shale blue	2030	Topeka lime	2800
shale drk	75	lime	2040	Top Topeka 2765	
shale blue	150	shale blue	2050	lime white	2835
shale grey	175	lime	2065	brkn sdy lime	2865
sand $\frac{1}{8}$ BPH	183	red rock	2070	$\frac{1}{8}$ BWPB 2845	
shale grey	190	shale grey	2080	show oil 2840-2855	
shale HFW 310	310	lime brkn	2095	lime	2975
sand	360	lime hrd	2110	lime white & grey	3010
shale blue	390	lime brkn	2120	lime	3015
sand	400	lime hrd	2140	shale blue	3020
shale blue	450	lime brkn	2150	red rock	3025
sand	465	red rock	2160	shale blue	3035
shale blue	500	lime	2205	shale	3037
sand	555	shale blue	2230	lime	3053
shale blue	565	lime	2240	Top Oswald 3037	
red rock	610	shale blue	2250	shale	3058
sand	630	brkn lime	2260	shale blue	3060
red rock	685	shale & lime shells	2300	lime sft-sh oil & gas	3062
shale red	715	shale blue & shells	2335	lime sft	3068
red rock	915	lime	2345	lime sft-oil & gas	3070
gyp	922	shale grey	2355	Hole filled 600' 3 hrs.	
anhydrite lime	960	shale blue	2385	lime hrd	3075
red rock	1115	lime	2395	Total Depth.	
shale blue	1150	shale blue	2400		
red rock	1205	lime	2405		
shale blue	1270	sh oil & wtr Hole filled			
salt & lime shell	1280	in 2 hrs 2400-05		Topeka lime 2765-3015	
salt	1300	brkn lime	2410	Oswald lime 3037-75	
salt & shale blue	1345	shale & shells	2430		
salt & red rock	1365	shale blue	2447		
salt	1565	lime	2452		
salt & lime shells	1585	shale blue	2455		
shale blue	1595	sdv shale	2475		
lime	1605	shalesome gas 4 BW	2485		
shale blue	1620	shale reddish	2495		
lime	1635	shale blue drk	2520		
shale blue	1645	lime	2525		
lime	1660	shale blue	2550		
shale blue	1670	lime	2560		
lime brkn	1690	shale blue	2570		
shale	1710	lime	2585		
lime hrd	1755	shale blue	2590		
red rock	1765	shale blue & shells	2595		
shale blue	1770	lime	2605		
lime	1805	shale green	2610		
shale rod	1825	lime	2650		
lime	1865	shale blue	2665		
shale blue	1875	lime shells & shale			
lime	1920	blue	2680		
shale blue	1925	shale blue	2690		
lime	1940	shale	2710		
shale	1950	lime	2725		
red rock	1960	shale blue	2740		
lime	1980	lime	2750		
lime	1985	shale blue	2765		
shale blue	1995	lime white & brown,			
lime	2015	show of oil	2769		