

STANOLIND OIL & GAS CO.
C.A. Mermis No. 33. 1

SEC. 5 T. 14 R. 15W
SE SW NE
330' NSL 990' EWL


Total Depth. 3079'
Comm. 8-12-37 Comp. 10-9-37
Shot or Treated.
Contractor.
Issued. 11-13-37

County. Russell

Cable 3079

CASING:

16" 41'
13" 560'6"
10³/₄" 927'9"
8⁵/₈" 2753'9"
7" 3070'



Elevation.

Production. Pot. 625 B.

Figures Indicate Bottom of Formations.

cellar	10	shale	2070	Corr. Top Oswald lime 3043
clay	20	lime	2080	1st oil show 3052-3055
sand	30	lime brkn	2140	lime sft oil 3060
shale blue	41	shale	2150	shale sft oil 3 061
shale & lime	60	red rock	2175	lime hrd 3062
lime	65	lime	2190	shale sft 3065
shale	210	shale	2200	shale blue sft 3067
sdv lime	215	lime	2235	shale 3069
shale lgt	230	red rock	2240	lime pay 3075
shale	235	shale	2250	lime 3077
lime	255	brkn lime	2265	lime & shale brkn 3079
sand	270	shale	2275	Total Depth.
shale	280	lime	2280	
lime shells	300	shale	2295	
sand HFW	335	lime	2300	
shale drk	380	shale grey	2325	
lime	405	lime	2330	First 4 hr pumped 107 oil,
shale blk	455	shale	2345	Second 4 hrs 104 oil
lime	460	lime	2355	no wtr.
shale	475	shale	2370	Prod 1st 24 hrs 625 B.
sand	545	lime	2380	
red rock	615	shale	2405	Oswald lime from 3043-3079
wtr sand	620	lime brkn	2420	
red rock HFW	912	shale	2425	
GYP	920	lime	2440	
lime anhydrite	955	shale	2450	
red rock	1035	lime	2470	
lime	1045	shale	2525	
red rock	1070	lime	2535	
shale	1085	shale	2539	
red rock	1135	lime	2550	
shale blue	1175	shale	2583	
red rock	1185	lime	2605	
lime	1188	lime brkn	2615	
red rock	1235	shale	2635	
shale blue	1315	shale & shells	2660	
salt	1585	lime	2670	
shale & shells	1625	shale	2715	
lime & lime shells	1685	lime brkn	2720	
lime	1695	shale	2728	
red rock	1730	lime brkn	2740	
shale & shells	1760	lime	2760	
red rock	1775	shale blk	2775	
shale	1785	sm oil sh 2774-79		
lime	1810	lime	2855	
shale	1825	HFW w/oil & gas 2848-2855		
red rock	1855	shale	2860	
brkn lime	1870	lime sdy 400' oil, 1200' 2888		
shale & shells	1905	W.I.H.		
shale	1915	lime	3010	
lime	1935	shale blue	3016	
shale	1955	lime	3035	
lime	1970	variegated shale	3038	
red rock	1975	lime	3041	
lime brkn	2015	shale variegated	3048	
shale	2050	lime	3060	
lime	2060	SIM Corr of hole 3060-3055		