


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.

STANOLIND OIL & GAS CO.
C.A. Mermis No. 22 12

SEC. 5 T. 14 R. 15W
NW SE NE
990' N SL 1650' E WL

Total Depth. 3086'
Comm. 9-22-37 Comp. 10-28-37
Shot or Treated.
Contractor.
Issued. 12-25-37 Cable Tools O-3086

County. Russell



Elevation.

CASING:
16" 43'
7" 3042'

Production. Pot. 786 B.
48 BW

Figures Indicate Bottom of Formations.

cellar-soil	10	lime white	1800	sm sh oil 2774-2776
shells	15	shale red & blue	1825	lime white 2820
sand(sm amt wtr)	21	lime white	1855	lime 2830
shale blue	43	shale blue	1866	lime white 2885
mud blue	75	lime white	1875	lime 2895
shale blue	250	sdv shale blue	1885	slate blue 2900
sand	260	lime sft	1900	lime 2910
shale white	275	lime	1930	lime white 2975
sand	285	lime white	1940	shale blue 2980
shale red	295	shale red & blue	1960	sdv lime-slt sh O&G 2990
shale blue	310	lime white	1985	shale blue 3007
sand white	370	shale grey	1990	Dodge - white lime 3022
shale blue	390	lime grey	2015	shale brown 3032
sand	400	shale grey	2020	lime 3034
shale blue	435	sdv shale grey	2030	shale green 3040
iron	440	lime	2050	lime(Top Oswald 3040)3061
sand white	450	shale blue	2055	Pay 3058-3060
shale blue	475	lime	2065	lime 3064
sand white	510	lime white	2070	shale blue 3066
sand grey	525	shale red	2085	lime grey 3068
shale red	545	lime white	2110	lime 3071
sand red	555	lime shells & shale	2115	shale 3074
SLCorr. 555-573		lime white hrd	2140	lime Tight 3078
shale red	590	shale grey	2145	lime Pay 3081
sand red	625	red rock	2170	brkn lime s/ small
shale red	670	lime	2175	pay 3086
red rock	700	red rock	2185	Total Depth.
sand	710	lime	2190	
red rock	730	lime white	2225	
shale red	800	lime	2240	
red rock	825	shale grey	2250	Oswald lime 3040-3086
shale red	890	lime	2256	
red rock	925	shale	2260	1st 4 hr test pumped 136 B.
shalk	928	lime	2285	43 BW
anhydrite lime	965	shale blue	2295	2nd 4 hr test pumped 131 B.
shale red	1100	lime	2310	5 BW
lime shells & blue shale	1145	lime shells & shale blue	2360	Potential 786 B., 48 BW.
shale blue	1165	shale blue	2370	
shale red	1200	lime	2375	
shale blue	1225	shale blue	2385	
shale red	1235	shale blue & lime shls	2455	
shale blue	1285	shale blue	2465	
salt white	1585	sdv shale	2475	
shale blue	1600	shale blue	2505	
lime	1610	SLCorr. 2505-2533		
lime & blue shale broaks	1645	brkn lime	2538	
lime white	1655	shale grey	2575	
shale grey	1675	lime	2590	
lime white	1685	shale blue	2605	
shale brown	1700	shale & shells	2625	
lime white	1704	lime shells & shale	2660	
shale blue	1715	shale blue	2715	
lime grey	1735	lime shells & shale blue	2738	
lime	1740	lime	2742	
shale blue	1750	shale blue	2745	
shale brown	1760	lime	2760	
lime grey	1785	shale blue	2774	