


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
 Union National Bank Bldg, Wichita, Kansas

STANOLIND OIL AND GAS CO.
 J.E. Baxter No. 26

SEC. 5 T. 14 R. 15W
 NE NE NW
 2310' W. of S.L. 2310 E of WL.

Total Depth, 3094
 Comm. 5-26-35 Comp. 7-16-35
 Shot or Treated.
 Contractor.
 Issued. 9-14-35.

County, Russell.



CASING.

16" 32' 85/8" 2772'
 13" 438' 7" 3045'
 10 3/4" 938'

Elevation.

Production. Pot. 74 bbls.

Figures Indicate Bottom of Formations

soil	10	shale light	2055	
sand	30	lime	2065	
shale	75	red rock	2070	
shale blue and brown	165	lime	2080	
sdv shale	175	shale	2100	
shale blue	195	lime	2110	
sand	220	shale	2135	
shale blue	250	shale red	2180	
sand HFW	275	lime	2195	
shale	280	1/4 BW	2185	
sand red shale	350	shale red	2205	
lime	360	red rock & shells	2240	
shale	415	lime and shale	2360	
lime	420	slate blue	2395	
shale	445	lime	2400	
lime	450	shale blue	2425	
sand HFW	470	shale grey	2445	
shale	490	lime	2450	
sand	505	red rock	2460	
red rock & shale	587	shale blue	2480	
lime hard	610	sdv shale 3 BWP	2490	
lime	620	shale dark	2520	
red rock	680	lime	2527	
lime	690	shale blue	2575	
red sand	700	lime and shale	2600	
red rock	770	GYP	2605	
lime	810	shale blue	2655	
red rock	940	shale grey	2720	
anhydrite	943	lime and shale	2780	
lime	978	CORING		
red rock	1115	lime grey tight	2782	
shale blue	1125	lime brown	2782 1/2	
lime	1135	show small amount oil		
shale	1160	lime grey hard	2785	
lime	1170	DRILLING		
red rock	1245	lime grey hard	2915	
shale blue	1320	lime grey sdy	2995	
salt	1565	shale 3BW 2960-70	3015	
red rock	1575	slate	3020	
lime	1600	lime	3025	
slate grey	1610	shale	3032	
lime	1625	shale Variegated	3044	Swabbed 1 bb per hr
shale blue	1630	lime Top Oswald	3045	7-17 400' oil in hole
lime	1665	CORING		no water.
shale blue	1670	lime grey med hard	3056	7-19- swabbed 4 hours
lime	1720	shale dark & soft	3058	at rate of 5 bbls., PH
red rock	1725	lime	3062	Acidized with 1000 gal.
lime	1750	show oil 3062		7-18-35 1st 24 H. on
shale grey	1780	shale	3070	potential
red rock	1790	lime	3075	7-22-35 Pumped 110 bbls.,
lime	1805	traces of pay		official Potential
shale grey	1880	lime and shale	3077	completed 7-24-35 74 bbls.
lime	1950	lime show oil	3078	Oswald lime 3045-3094
shale blue	1975	DRILLING		
lime white	1985	lime hard tight	3080	
shale grey	1995	100' oil in hole		
shale blue	2015	lime hard grey	3094	
lime grey	2030	filled up 100' with oil in		
		2 hours. Total Depth.		