


STANOLIND OIL & GAS CO.
J.E. Baxter No. 13 Q

SEC. 5 T. 14 R. 15W.
SE NE NW
1650' N of S.L. 2310' E of W.L.

Total Depth. 3072
Comm. 3-16-38 Comp. 4-21-38
Shot or Treated.
Contractor.
Issued. 6-4-38 Cable 3072'

County Russell.



CASING.

16" 44' 7" 3042'

Elevation.

Production. Pot. 332 B.
No wtr.

Figures Indicate Bottom of Formations.

cellar soil	8	lime	1870	lime	3044
post rock	15	shale	1885	Top Oswald 3041	
sdv shale	32	lime	1920	lime	3061
shale blue	155	shale	1927	shale	3068
shale light	170	lime	1940	lime	3072
shale blue	190	shale & lime shells	1985	Total Depth.	
sand 15 BWPB	205	shale	1995		
shale red	250	lime hard	2025		
sand 25 BWPB	260	red rock	2040	Oswald lime 3041-3072	
shale red	280	lime	2075		
shale grey	320	shale red	2085	1st 4 hours 67 Oil no wtr	
sand	335	lime	2145	2nd 4 hours 55 oil no wtr.	
shale grey	370	shale red	2160		
shale blue	380	shale red	2170		
shale brown	395	lime	2215		
shale grey	415	shale red	2230		
shale blue	440	lime	2250		
sand	450	shale	2260		
shale blue	455	lime	2300		
sand	465	shale and shells	2320		
red rock	470	lime	2330		
shale blue hole cav.	477	shale blue	2340		
shale red	495	lime	2355		
sand	520	shale blue	2375		
quick sand	545	lime	2385		
sand	571	shale	2395		
red rock	576	lime	2407		
shale red	620	shale red blue and			
Dakota sand	660	brown	2465		
red rock 12 BWPB	725	lime	2470		
sand HFW	740	sand	2475		
red rock	850	1 1/2 BWPB			
shale red	890	shale	2500		
red rock	932	lime	2525		
Anhydrite lime	970	shale	2555		
shale red	995	lime	2565		
red rock	1095	shale & lime shells	2580		
shale red	1130	lime	2585		
shale brown	1170	shale	2595		
red rock	1200	lime	2620		
shale blue & brown	1230	shale	2625		
red rock	1255	lime	2635		
shale blue & brown	1315	shale	2700		
salt	1575	lime	2720		
shale blue	1585	lime shells & shale	2745		
lime	1620	shale	2769		
shale blue	1625	lime	2775	Small sh oil	
lime hard	1635	lime	2933		
shale blue	1640	shale	2935		
lime	1660	lime	2970		
shale	1670	sand lime	2977	1 BWPB	
lime	1685	lime	2990		
shale red & blue	1705	shale blue	2995		
red rock	1720	lime	3002		
lime	1745	shale	3010		
shale	1760	lime	3029		
lime	1795	shale grey	3033		
shale red	1830	conglomerate	3041		