

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

35326


Location NW SE SE

Sec. 5 T. 14 R. 15W.

## Casing Record

County- Russell.

20" 10" 922 Farm- Co. Portland No. 28  
 15 1/2" 8 1/2" 2780 Company- Midwest Exploration Co.  
 12 1/2" 550 65/8" 3036 Contr.-  
 12 1/2" 550 53/16" Comm.- 2/26/29. Comp.- 4/8/29.  
 Total Depth 3106' Shot Quarts Between  
 Correspondence Regarding This Well Should Be Referred to



Figures Indicate Bottom of Formations. Elevation Initial Production 30 bbls. per day.

Figures Indicate Bottom of Formations.  
 Date Issued. 4/20/1929.

Formation	Depth	Formation	Depth
shale	50	shale blue	2360
shale blue	85	lime	2370
sand shale	190	shale blue 8" pipe	2414
sand water 8 BW	215	lime	2430
red rock & sandy shale	260	shale black	2440
red rock	280	lime	2445
shale blue	300	shale blue	2460
sand HFW	350	lime	2465
shale blue	470	shale blue	2490
sand	520	lime brkn 3 BW	2505
red rock	615	shale black	2535
12 1/2" at 545'		lime	2540
sand red	720	lime brkn	2560
red rock	920	shale black	2575
lime	960	lime	2585
red shale	1140	shale black	2600
shale blue	1160	lime	2615
red rock	1240	shale blue	2625
shale	1300	lime	2635
salt	1510	shale blue	2645
shale	1600	lime	2670
salt	1620	shale black	2685
shale	1635	sandy shale blue	2705
lime	1660	lime	2720
shale	1665	shale black	2725
lime	1700	shale blue & lime	
red rock	1720	shells	2740
lime	1735	8 1/2" at 2743'	
shale	1750	sandy shale blue	2745
lime	1760	lime	2755
shale	1765	shale blue	2772
lime	1780	lime	2780
shale	1785	Show oil UR 8"	
lime	1810	lime	2873
shale	1820	shale blue	2876
lime	1830	lime	2900
red rock	1860	shale blue	2904
lime	1900	lime	2970
shale	1920	sandy lime brkn	2980
lime	1940	3 BW	
red rock	1950	lime	3005
lime	1975	shale blue	3015
shale	1980	lime (Dodge)	3028
lime	1990	shale red	3032
shale	2000	6" pipe at 3036'	
lime	2065	shale brown	3036
shale blue	2080	lime	3037
lime	2165	blue & green shale	
red rock	2185	lime	3046
lime	2210	lime top of Oswald	3054
shale blue	2220	lime hrd	3063
lime	2235	shale blue	3073
red rock	2245	lime hrd	3074
lime shells & shale	2295	lime porous oil	3077
lime	2325	lime brkn	3082
shale black	2330	shale red	3087
lime	2345	lime brkn	3106
		TD	3106'