

GULF OIL CORP OF PENN.
Carl Ehrlich No. 3

SEC 1 T 14 R. 15W.
NW SW NW


DEEPENING RECORD

Total Depth. 3296'
Comm. 2-20-36 Comp. 4-7-36
Shot or Treated. 1000 gal
Contractor.
Issued. 5-12-38

County. Russell.

CASING.
15 1/2" 301'
13" 600'
10" 925'
8 5/8" 2513'
7" 3045'
5 1/2" 3295'

Mar 12 1938



Elevation.

Production. Pot. 709 B.O.
5 BW

Figures Indicate Bottom of Formations.

cellar	8	shale	2195	line	3079
clay yellow	40	lime	2215	shale	3080 1/2
shale blue	175	red rock	2225	line	3095
mud blue	220	lime	2240	Total Depth.	
sdv shale	235	shale	2245		
red rock	330	lime	2260		
shale blue	355	shale blue	2265	Oswald line 3044-3095	
sand	370	lime	2305		
shale blue	430	shale	2320		
sand	455	lime	2340		
shale blue	470	shale	2355		
sand	485	lime	2359		
shale blue	515	shale	2364		
sdv shale	535	shale blue	2378		
red rock	585	shale	2395		
sand	600	lime	2405	Comm. 3-1-37 Comp. 4-1-37	
shale red	705	shale	2438	Prod. Pot. 830 B.O.	
sand	720	lime	2445	250 Wtr.	
shale red	765	red rock	2463		
sand	800	lime	2468	Old T.D. 3095	
shale red	915	sand	2492	Oswald line 3095-?	
anhydrite	925	shale blue	2500	Corham sand 3295-96	
lime	960	shale	2503	Total Depth.	
red rock	1110	lime	2507		
shale blue	1155	shale	2510		
red rock	1230	lime	2527	Production before	
shale blue	1270	shale	2554	1000 gals acid 341 B.	
lime	1280	shale blue	2560	Potential and 43 Wtr.	
shale blue	1300	lime	2583		
salt	1570	shale	2590		
shale	1580	lime	2615		
shale and shells	1630	shale	2625		
anhydrite	1660	lime	2645		
shale blue	1670	shale	2660		
lime	1700	lime	2665		
shale blue	1710	shale	2707		
red rock	1715	lime	2730		
lime	1765	shale blue	2757		
shale blue	1780	lime	2803		
lime	1825	lime hard	2832		
red rock	1830	lime	2845		
lime	1875	shale	2850		
shale blue	1880	lime	2860		
lime	1960	shale	2862		
shale blue	1965	lime	2938		
red rock	1980	shale	2945		
lime broken	2000	lime	2995		
shale and shells	2015	shale green	3005		
lime	2035	lime	3020		
shale	2045	shale	3044		
lime	2085	Oswald lime	3056		
shale	2100	shale	3058		
lime	2150	lime	3061		
red rock	2160	shale	3067		
lime	2180	lime	3075		
sdv lime	2190	shale	3076		