

National Refining, ~~#22~~ # 3-A East Reinhardt
NE NW NE, 36-14S-15W
Elev. 1741'

Pennsylvanian Conglomerate 3157'-3163'
3157-3163 White to brown limestone with rare included
sand grains.

Arbuckle Top 3163' Penetration 15' Subsea -1422'

Post Boyce 3163-3178' TD
3163-3166 White coarsely crystalline dolomite with
scattered coarse sand grains.
3166-3171 Dolomite, medium to coarse, sandy. White
and clear feldspars (Orthoclase and
Microcline) common.
3171-3178 Dolomite, medium to coarse, with about
20% included medium and coarse sand.

ML & RFW