

7-14-16W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

Company- RUDY HERMAN
Farm- Schippers No. 1

SEC. 7 T. 14 R. 16W
NE SE NE

Total Depth. 3475'
Comm. 12-23-60 Comp. 1-3-61
Shot or Treated.
Contractor. Woodman & Iannitti Drlg.
Issued. 4-22-61

County Ellis
KANSAS



CASING:
8 5/8" 170' cem w/130 sx.
5 1/2" 3462.5' cem w/125 sx.

Elevation. 1942' DF

Production. 50 BOPD

Figures Indicate Bottom of Formations.

COMPLETE DRILLERS LOG NOT AVAILABLE:

Occasional dark brn to blk oil stain in buff crystalline limestone 3182-3186

Rare spotted lgt brn oil stain in buff crystalline limestone 3205-3208

Scattered rich brn oil stain in buff oolitic limestone 3235-3240

Occasional lgt brn oil stain in buff matted oolitic & oolitic limestone 3254-3258

Occasional lgt brn oil stain in buff oolitic limestone 3300-3305

Buff to lgt brn sucrose dolomite with cherty dolomite & sharp oolitic chert 3461-3463
Rotary Total Depth 3463
Total Depth 3475

TOPS: SAMPLE	
Anhydrite (Driller)	1080
Topeka	2939
Haebner	3161
Toronto	3179
Lansing-Kansas City	3205
Arbuckle	3461

DST #1 3220-3242', op 1 hr, weak, steady blow 1 hr, rec. 120' muddy water, IBHP 960#/20 min. IFP 0#, FFP 85#, FBHP 900#/20 min.

DST #2 3245-3260', op 1 hr, strong blow thruout test, rec. 780' gas, 360' muddy froggy oil, IBHP 530#/20 min, IFP 80#, FFP 130#, FBHP 470#/20 min.

DST #3 3290-3305', op 1 hr, fair, steady blow for 1 hr, rec. 150' water, IBHP 920#/20 min, IFP 15#, FFP 40#, FBHP 800#/20 min.