

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-14-1648

Company- CLINTON OIL & JONES-GEBERT OIL INC.
Farm: Robben No. 1

SEC. 15 T. 14 R. 16W
NE SW NW

Total Depth. 3485'
Comm. 3-7-64 Comp. 3-19-64
Shot or Treated.
Contractor. Jones-Gebert Oil Inc.
Issued. 6-20-64

County Ellis
KANSAS



CASING:

8 5/8" 200' cem w/ 160 sx
4 1/2" 3484' cem w/ 160 sx

Elevation. 1922' KB

Production. 83 BOPD / 2% WTR

Figures Indicate Bottom of Formations.

sand, shale & clay	100
shale & sand	150
shale	200
shale & shells	465
shale	1470
shale & shells	1707
shale	2035
lime	2090
lime & shale	2568
shale	2760
lime & shale	3166
lime	3220
Kansas City	3235
lime	3442
Arbuckle	3485 RTD
Total Depth	

TOPS: SCOUT	
Anhydrite (Smp)	1040
Heebner	3111
Toronto	3129
Lansing	3158
Base Kansas City	3395
Conglomerate	3404
Reworked Arbuckle	3444
Arbuckle	3450