

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CINOIL, INC.
Farm - Berens "A"

No. 1

SEC. 1 T. 14 R. 16 W
SE NW NW

Total Depth. 3468'

Comm. 7-25-45

Comp. 9-13-45


Shot or Treated.

Contractor. Holm Drlg. Co.

Issued. 11-24-45

County. Ellis

KANSAS



Elevation. _____

Production. Dry

CASING:

8 5/8" 1020'
5 1/2" 3468'

Figures Indicate Bottom of Formations.

shale & shells	525	coring shale & lime	3387
shale & iron shells	1010	coring shale	3389
anhydrite	1050	coring	3398
shale & shells	1380	coring shale	3405
salt shale shells	1565	coring	3415
salt & shale shells	1665	coring conglomerate &	
shale & lime shells	1730	chert	3426 1/2
lime & shale brks	1940	conglomerate & chert	3436
lime lgt med	1970	coring conglomerate	3446
lime & shale brks	2055	coring conglomerate &	
lime lgt hrd	2275	chert	3463
lime & shale brks	2495	coring	3468
lime lgt hrd	2505	Total Depth.	
lime & shale brks	2783		
lime lgt hrd	2815	Tops:	
shale hrd	2865	Anhydrite	1010
coring	2891	Base Anhydrite	1050
coring shale	2892	Salt (Wellington)	1380
coring lime hrd	2902	Base of Salt	
coring lime	2920	(Wellington)	1665
coring	2934	Topeka Lime	2890
coring lime hrd	2942	Lansing K. C.	3154
coring lime	2948	Conglomerate	3415
coring lime hrd	2950 1/2	Arbuckle Lime	3426
coring lime	2985		
coring lime hrd	2994	Oil Shows:	
coring lime	3013	3154-69'; 3182-84'; 3189-90';	
coring	3020	3224-27'; 3240-40 1/2'; 3316-24';	
shale	3024	3339-42'; 3426-36'; 3436-39';	
lime & shale brks	3030	3441-46'; 3450-52'.	
lime & shale hrd	3050		
lime & shale	3090	Formations not shown on drilling	
lime	3100	report for some sections cored.	
coring lime hrd	3112		
lime hrd	3117		
shale	3118		
coring shale	3121		
coring lime	3123		
lime & shale	3128		
coring lime hrd	3137		
coring lime	3140		
coring shale	3154		
lime hrd	3165		
lime	3169		
coring lime	3176		
coring	3177 1/2		
coring shale	3180		
coring lime	3192		
coring lime hrd	3220		
coring lime	3223		
coring lime & shale	3235		
coring	3242		
coring lime hrd	3249		
lime gy hrd	3306		
coring lime hrd	3309		
coring	3318		
coring lime	3320		
coring lime hrd	3334		