


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BURCH DRILLING CO., INC.
Farm- Kuhn No. 1

SEC. 5 T. 14 R. 16W
NW NE NW

Total Depth. 3470'
Comm. 2-10-59 Comp. 2-19-59
Shot or Treated.
Contractor. Burch Drlg.
Issued. 7-11-59

County Ellis
KANSAS



Elevation. 1954' KB

Production. 101 BOPD

CASING:

8 5/8" 190' cem w/150 sx.
4 1/2" 3468' cem w/125 sx.

Figures indicate Bottom of Formations.

shale & shells	1060
Anhydrite	1102
shale	1400
shale & lime strks	1820
lime & shale	3200
lime	3430
cherty lime	3460
lime	3470 RTD
Total Depth	

TOPS:

Anhydrite	1058
Heebner	3164
Toronto	3184
Lansing	3210
Base Kansas City	3405
Arbuckle	3469

DST #1 3202-3230', op 30 min, rec. 10'
mud, IBHP 940#/30 min., IFP 0#, FFP 0#,
FBHP 810#/30 min.

DST #2 3232-3273', op 1 hr, rec. 910'
gas plus 90' very heavy oil gas cut mud
plus 150' froggy oil plus 156' oil.
IBHP 1120#/30 min, IFP 40#, FFP 170#,
FBHP 940#/30 min.

DST #3 3280-3308', op 1 hr, rec. 39'
watery mud. IBHP 1130#/30 min., IFP 0#,
FFP 0#, FBHP 570#/30 min.