

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- BURCH DRILLING CO., INC.  
Farm- Kuhn No. 2

SEC. 5 T. 14 R. 16W  
SE NW NW

Total Depth. 3510'  
Comm. 6-23-59 Comp. 7-3-59  
Shot or Treated.  
Contractor. Burch Drlg.  
Issued. 9-12-59

County Ellis

KANSAS



Elevation. 1958' KB

Production. Dry

CASING:

8 5/8" 190' cem w/150 sx.

Figures Indicate Bottom of Formations.

shale	500
shale & shells	1068
Anhydrite	1107
shale	1335
shale & shells	1805
shale & lime	2130
lime	2713
lime & shale	2975
lime	3510 RTD
Total Depth	

TOPS:

Anhydrite (scout)	1068
Heebner	3166
Toronto	3186
Lansing	3212
Base Kansas City	3404
Arbuckle	3462

DST #1 3552-3562, op 30 mins., rec. 15'  
mud, all pressures were zero.

DST #2 3261-3273, op 30 mins., rec. 15'  
mud, all pressures were zero.

DST #3 3275-3315, op 1 hr., rec. 30' mud,  
IBHP (30 min) 1090#, IFP 0#, FFP 0#,  
FBHP (30 min) 600#.

DST #4 3462-3475', op 30 mins., rec. 12'  
slightly oil specked mud. IBHP (30 min)  
1055#, IFP 0#, FFP 0#, FBHP (30 min) 670#.

DST #5 3464-3483, op 1 hr., Rec. 25'  
slightly oil specked mud. IBHP (30 min)  
1070#, IFP 0, FFP 0#, FBHP (30 min) 665#.

DST #6 3483-3510 op 1 hr, rec. 480'  
rec. 480' muddy salt water. IFP 40#,  
FFP 150#, FBHP (30 min) 965# (NO IBHP).