


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

Company - THE ATLANTIC REFG. CO.
Farm - Michael P. Dreiling No. 3

SEC. 22 T. 14 R. 16W
SW SW SW

Total Depth. 3377½ PB 3324
Comm. 5-26-51 Comp. 7-3-51
Shot or Treated.
Contractor.
Issued. 8-11-51

County. Ellis
KANSAS



CASING:
9 5/8" 196.08' cem. w/200 sx
7" 3354' cem. w/200 sx

Elevation. 1853 DE

Production. Pmp. 142 BOPD 8/hrs.
1% wtr.

Figures Indicate Bottom of Formations.

surface hole	197
shale & shells	425
shale	450
sand	570
red bed & shale	690
red bed	942
anhydrite	985
shale & shells	1300
shale & salt	1425
salt	1540
shale & lime	1635
lime shells	1750
lime & shale	2125
shale & shells	2200
lime	2240
lime & shale	2515
shale & shells	2750
lime & shale	2805
lime	2870
shale & lime	3070
lime	3377½
Total Depth PB 3324	

Scout Tops:
Heebner 3048
Lansing 3077
Conglomerate 3345
Arbuckle 3347

Producing Zone: 3239-3244'
(Lansing-K.C.)