


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- GLICKMAN OIL COMPANY
Farm- Tholen No. 2

SEC. 22 T. 14 R. 16W
NE SW SE

Total Depth. 3399
Comm. 2-6-51 Comp. 2-20-51
Shot or Treated.
Contractor. The Veeder Supply & Development Co.
Issued. 8-21-54

County Ellis
KANSAS



Elevation. 1888

8 5/8" 216' cem. w/130 sx
5 1/2" 3422' cem. w/125 sx, 4' Off Bottom
Figures indicate Bottom of Formations.

Production. IPP 318 BO / NW

surface soil	40
sand & shale	80
shale & shells	120
sand, shale & shells	150
shale & shells	575
sand & shale	650
redbed & shale	770
redbed	990
Anhydrite	1025
shale & shells	1385
shale & salt	1660
shale & lime	1800
lime	1910
shale & lime	2120
lime	2170
shale & lime	2530
lime, shale & shells	2680
lime & shale	2915
lime cherty	2990
lime	3399
Total depth	

Tops:	
Topeka	2866
Heebner	3086
Lansing	3135
Conglomerate	3380
Arbuckle	3388