

WELL LOG BUREAU • KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

CONTINENTAL OIL CO.
John A. Baumrucker No. 1.

SEC. 25 T. 14 R. 16W.
NE 1/4 SW
330' So. and 330' W. of
the center.

Total Depth. 3394
Comm. 11-14-37 Comp. 12-11-37
Shot or Treated.
Contractor. Parker Drlg. Co.
Issued. 3-5-38

County Ellis.



CASING.

Elevation.

13" 361'8" 95/8" 905'10"

Production. DRY.

Figures Indicate Bottom of Formations.

rock sand and clay	50
red bed and shale	245
sand hard	275
red bed	375
water sand	515
shale	577
sand	590
shale	620
shale blue red bed and	
iron pyrite	700
shale	745
red bed	784
red bed shale and iron	875
red bed shale and iron	
pyrite	894
anhydrite	930
lime shells	945
sand	960
red rock shale parytise of	
iron	1100
red bed shale and lime	
shells	1240
shale and shells	1340
shale and salt	1530
shale and lime	1590
shalo lime shells	1630
broken lime	1700
lime and shale	1870
broken lime and shale	1944
lime and shale	1999
lime broken	2217
broken lime and shale	2317
broken lime	2400
shale and lime	2480
broken lime and shalo	2583
shale and lime	2633
shale and shells	2718
shale and lime shells	2765
broken lime	2792
broken lime and shale	2837
broken lime	2884
lime	3069
broken lime and red	
shale	3076
lime	3078
lime soft small oil show	3084

lime	3095
lime soft small oil sh	3098
lime	3130
broken limo	3148
lime	3282
shale	3290
conglomerate & chort	3303
conglomerate	3364
Arbuckle	3390
cherty lime & conglomerate	3394
Total Depth.	

12-6-37

Lansing lime show oil at 3078 to 3084
and from 3095-3098

12-10-37

In Arbuckle lime no show oil from
3364-3370

Top of Anhydrite	894
Top of Lansing lime	3010
Top Conglomerate	3200
Top Arbuckle	3364

3076
1814
1262