


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HONAKER-DAVIS DRIG. CO., ET AL
Farm- Schulte No. 1

SEC. 26 T. 14 R. 16W
SW SE NW

Total Depth. 3416'
Comm. 6-7-56 Comp. 6-20-56
Shot or Treated.
Contractor. Honaker-Davis Drig. Co.
Issued. 9-22-56

County Ellis
KANSAS



Elevation. 1879' KB

Production. 18 BOPD

Figures Indicate Bottom of Formations.

clay-gravel	20
sand-gravel	60
sand	90
shale-shell strks sand	195
shale-red bed	250
r3d bed-shale	480
sand-Dakota	600
red bed	980
Anhydrite	1010
shale-shells	1400
shale-shells ¹ / ₂ salt	1690
shale-anhydrite-shells	1740
shale-lime strks	1850
lime-shale	2250
shale-lime strks	2270
lime-shale	3121
lime	3363
lime-chert	3385
Conglomerate	3386
Arbuckle	3416
Total Depth	RTD

T OPS:
Heebner 3073
Toronto 3094
Lansing-Kansas City 3125
Conglomerate 3354
Arbuckle 3386

DST #1- 3107-3145'
Open: 30" - closed- 20"
Blow: Weak 4" & 1".
Rec. 10' mud
Pres: BHP 70#

DST #2- 3196-3228'
Open: 20" - Closed: 20"
Blow: Weak 8" & 1"
Rec.: 65' mud
Press.: BHP 930#

DST #3 - 3388-3393'
Open: 20" -Closed: 30"
Blow: Weak 1"
Rec.: 10' mud
Press.: BHP 640#

DST #4- 3393-3403'
Open: 20" - Closed 30"
Blow: Weak 2"
Rec.: 8' mud
Press.: BHP 1030#

DST #5- 3403-3413'
Open: 60" - Closed 30"
Blow: Good
Rec.: 308' SM & GC oil
Press.: IFP Off
FFP 120#
BHP 830#