

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- SUN OIL COMPANY
Farm- Heyl No. 1

SEC. 26 T. 14 R. 16W
SW SW SW

Total Depth. 3105
Comm. 3-23-53 Comp. 4-3-53
Shot or Treated.
Contractor.
Issued. 5-9-53

County Ellis

KANSAS



CASING:
8 5/8" 678.48' cem w/400 sx
5 1/2" 3105' cem w/150 sx

Elevation. 1829 D.F.

Production. Pmped 85.26 bbls in
8 hrs. & no wtr

Figures Indicate Bottom of Formations.

sand	70
clay	245
shale, shells	340
sand	400
shale, shells	445
sand	560
shale, red bed	570
red bed	885
anhydrite	965
shale, shells	1575
shale, lime	3018
shale (Heebner)	3023
lime, shale	3037
lime (Toronto)	3051
shale (Douglas)	3065
lime Lansing	3083
shale	3086
lime	3090
shale	3095
lime	3099
shale	3105
Total Depth	

Tops: Electric log
Heebner 3018
Lansing 3065

Casing Perforations:
3065-3080' 60 shots acid:
2000 gals 3065- 3080.

Cores: 3069-3105

I. P. (Corp. Commission test.
4-22-53 pumped 85.26 bbls oil
in 8 hrs, no water)(256 b.p.d.)