


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- D. G. HANSEN  
Farm- Wellbrock No. 1

SEC. 31 T. 14 R. 16W  
SW SW SW

Total Depth. 3528 R.B.  
Comm. 9-8-53 Comp. 9-20-53  
Shot or Treated.  
Contractor. C-G Drlg Co.  
Issued. 10-31-53

County Ellis  
KANSAS



CASING:  
8 5/8" 1095.86' L.I.

Elevation. 1933 R.B.

Production. Dry

All Measurements from the top Figures Indicate Bottom of Formations.  
of the rotary bushing.

shale, sand	0 - 580
sand	690
red bed	830
red bed, shale	1058
anhydrite	1068
shale, lime	1480
shale	1790
lime, shale	2999
lime	3060
lime, shale	3340
lime	3378
lime, shale	3495
lime	3528
Total Depth	

Tops:	
Topeka	2939
Heebner	3167
Toronto	3187
Lansing-Kansas City	3216
Conglomerate	3460
Arbuckle	3478

Wildcat test.

Show poor porosity & staining & carried no odor	3236-39
Brkn poro., no odor & no stain	3279-90
No stain & no odor in good oolitic porosity	3297-3300
Show poor porosity & no stain	3308-11
No stain & poor fossiliferous poro.	3348-53
Show no odor & carried no staining in poor porosity.	3373-77

Reamed 9" hole to 13 3/4"  
from 0' to 1068'