

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- RUDY A. HERMAN
Farm- Baumrucker No. 1

SEC. 36 T. 14 R. 16W
SE NE NW

Total Depth. 3402'
Comm. 4-9-59 Comp. 4-18-59
Shot or Treated.
Contractor. Shields Drlg. Co.
Issued. 6-27-59

County Ellis

KANSAS



Elevation. 1846' RB

CASING:
8 5/8" 264' cem w/175 sx.

Production. Dry

Figures Indicate Bottom of Formations.

surface soil, sand & rock	201
shale	468
sand	585
shale and shells	875
red bed, shale	934
Anhydrite	970
red bed, shale & shells	1330
shale, shells and salt	1550
shale w/line streaks	1640
line and shale	2883
line	3367
Conglomerate	3402
Total Depth	

TOPS:

Topeka	2820
Heebner	3047
Toronto	3064
Lansing-Kansas City	3099
Conglomerate	3339

DST #1 3080-3113', op 1 hr, weak blow
20 min. rec. 10' rotary mud, BHP 960#/20 mins.

DST #2 3117-3180', op 1 hr, w/weak blow
for 40 min. rec. 10' rotary mud w/V.S.S.
free oil on top tool. BHP 395#/30 mins.

DST #3 3180-3250', op 1 hr., w/weak blow
for 1 hr., rec. 60' rotary mud, BHP 925#/30 min.