

Stephen C. Robben

Box 426

Victoria, Kansas 67671

Phone 913-735-9405

T & D Oil Co.
Rohleder # 2
27-14^S-16^W
SE-NW-~~SE~~ SW
Ellis Co. Kansas

Workover Report

7-14-82 Rigged up Express Well Service. Run collar log, T.D. 3382'. Set bridge plug at 3330' (Baker Model P-1). Swabbed hole dry. Perforated 1 shot at 3308', 3285', 3269', and 3245'. No fluid natural. Treated zones with 2000 gals. of acid (20% gelled). Treated at 7 BPM 1700# pressure. Dropped 2 balls after 1000 gals. of acid. 97 BBL load. Let shut in 1 hr. Bled back 14 BBL of load.

Swab down	63.0	BBL	
20 min test	3.0	BBL	60% oil

7-15-82 1100' of fluid in hole (500' oil 600' wtr.).

Swab down	20.0	BBL	
30 min	3.0	BBL	80% oil
30 min	3.0	BBL	80% oil
30 min	1.5	BBL	80% oil
1 hr. 15 min	3.0	BBL	80% oil
1 hr.	1.5	BBL	70% oil

Retreated zones with 4000 gals. of acid (20% gelled). Treated at 7 BPM 400# pressure. Dropped 2 balls after 2000 gals. pressure increased to 1950# at 7 BPM. ISIP 300#. Shut well in 1 hr. Well blew back 35 BBL of load. 155 BBL load.

Swab down	48.0	BBL	
30 min test	3.20	BBL	80% oil

7-16-82 900' of fluid (500' oil 400' wtr.). Perforated from 3307'-09', 3284'-86', 3268'-70', and 3244'-46' (3/ft SSB's). Run tubing and rds.