

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BIRMINGHAM-BARTLETT DRIG. CO.
Farm- Ray Braun No. 3

SEC. 2 T. 14 R. 17W
SE NW NE

Total Depth. 3466'
Comm. 1-10-58 Comp. 1-20-58
Shot or Treated.
Contractor. Birmingham-Bartlett Drig. Co.
Issued. 3-22-58

County Ellis
KANSAS



CASING:
8 5/8" 1117' w/550 sx cem.
5 1/2" 3457' w/150 sx cem.

Elevation. 1932' DF

Production. 50 BOPD

Figures indicate Bottom of Formations.

clay, rock	70
shale, shells	160
shale	430
sand, shale	560
sand	775
shale, shells, red bed	1050
red bed, shells	1102
Anhydrite	1145
shale, shells	1700
lime, shale	2905
lime	2960
lime, shale	3040
lime	3459 RTD
lime	3466
Total Depth	

TOPS: Anhydrite	1104
Heebner	3152
Toronto	3170
Lansing	3198
Arbuckle	3454

DST #1 3184-3210. Open 30 mins.
Rec. 30' mud, trace oil. BHP 0

DST #2 3208-30. Open 1 hr. Rec.
630' gas, 240' very Heavy oil &
GCM. BHP 380#.

DST #3 3263-71. Open 35 mins.
Rec. 50' watery mud. BHP 510#.