

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - R. G. PIPER ET AL
Farm - Ray Braun No. 1.

SEC. 2 T. 14 R. 17 W
NE NW NW

Total Depth. 3456'
Comm. 11-5-44 Comp. 12-1-44
Shot or Treated.
Contractor. Thos. H. Allan
Issued. 12-23-44

County. Ellis
KANSAS



Elevation. _____

Production. 2 Bbl/hr

CASING:
12 1/8" 67'
8 5/8" 1116'
5 1/2" 3454'

Figures Indicate Bottom of Formations.

surface sand	20	hole filled 800' of
shale dk	50	oil in 8 hrs
shale limy	200	hole filled 1200' of
Dakota pyritic dk sdy		oil in 15 hrs
shale	220	
sand fine wh	310	
mud red	350	
buff sdy concretions	380	
sandstone	490	
shale pyritic &		
concretions	550	
sand wh	650	
shale & sandstone	710	
sand red	730	
sandstone pyritic	825	
Permian red beds	1100	
gypsum & shale	1108	
anhydrite hd	1140	
red beds	1270	
shale gy & red	1320	
shale & salt	1790	
shale & anhydrite	2000	
shale red	2040	
Ft. Riley limestone	2110	
shale	2125	
Florence Flint	2150	
shale	2205	
lime hd & chert blk	2230	
shale & shells	2310	
Cottonwood limestone	2350	
shale red	2376	
Neva limestone	2410	
shale & lime shells	2890	
shale sdy	2908	
Topeka limestone	2940	
limestone & shale	3042	
lime wh lithographic	3060	
shale & limestones	3170	
shale blk	3175	
shale & shells	3200	
shale red	3214	
Lansing limestone	3236	
lime porous oolitic(wtr)	3241	
lime wh hd	3278	
lime porous (wtr)	3285	
shale	3292	
lime cherty	3299	
shale	3303	
lime porous oolitic(wtr)	3308	
lime wh & shale partings	3425	
lime dense buff	3430	
shale & lime wh	3440	
shale red & green	3451	
Arbuckle dol. & ool. chert	3454	
ran 5 1/2" csg & standardized		
dolomite partly oil		
saturated & chert	3456	
Total Depth.		