

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.


TWIN DRG. CO. ET AL
Goetz No. 3.

SEC. 3 T. 14 R. 17W
NE NW SE

Total Depth. 3530'
Comm. 7-14-38 Comp. 8-10-38
Shot or Treated. 1000, 2000 & 4000 Gals.
Contractor. Twin Drlg. Co.
Issued. 9-10-38

Rotary 3503 $\frac{1}{2}$
Cable 3530

County. Ellis



Elevation.

CASING:
10" 110'
5 $\frac{1}{2}$ " 3504'

Production. Pot. 1573 B.

Figures Indicate Bottom of Formations.

cellar	8	shale	2654
soil yellow	20	lime lgt hrd	2685
sand	35	shale & shells blue	2734
shale	145	shale & shells blue med	2759
shale & shells med	230	lime lgt hrd	2775
shale shelly	425	shale & shells blue	2788
shale blue & shells med	450	shale	2802
sand & ir on shells red	500	lime lgt med	2818
shale & shells blue	650	lime lgt hrd	2858
sand sft	800	lime lgt & shale brks med	2876
shale blue med	830	lime lgt hrd	2945
shale red med	920	shale & shells blue med	2980
shale red	1060	lime lgt med	3018
shale red med	1177	lime lgt hrd	3180
anhydrite hrd	1212	lime brkn	3190
shale red	1243	lime hrd	3208
shale shelly	1265	lime lgt hrd	3255
shale blue	1333	lime lgt & shale brks med	3272
shale & shells blue med	1375	lime lgt hrd	3284
lime lgt hrd	1390	lime brkn med	3292
shale & shells blue	1414	lime lgt hrd	3315
shale & shells blue med	1450	lime lgt med	3325
shale & shells red med	1492	lime lgt hrd	3377
shale & lime shells	1567	lime med hrd	3410
shale & limoshells blue med	1610	lime lgt hrd	3504
salt, shells & shale med drk	1660	conglomerate	3505 $\frac{1}{2}$
salt, shale & shells	1792	dolomite (Sil. lime) sat.	3507
salt & shale	1815	Corr. in meas. Top Sil.	3504.
lime	1835	total depth of rotary	3503 $\frac{1}{2}$
lime lgt med	1938	Standard Tools	
lime brkn med	1995	lime	3505 $\frac{1}{2}$
lime lgt cherty hrd	2015	lime med	3511 $\frac{1}{2}$
lime lgt hrd	2027	lime sft (sh free oil)	3514
shale & lime shells	2038	lime med	3516 $\frac{1}{2}$
lime lgt hrd	2053	lime hrd	3518
shale & shells blue med	2062	lime sft	3526
shale & shells blue	2075	lime med	3530
lime lgt med	2165	Total Depth.	
lime lgt hrd	2495		
shale & shells blue	2505		
lime lgt hrd	2640	Swab 8 b. hr nat	
shale	2645	1000 gals acid 13 BPH	
lime lgt hrd	2650	2000 Gals. acid 30 BPH	
		4000 Gals. Pot. 1573 B. Day	