


WATCHORN OIL & GAS CO.  
Braun No. 2

SEC 3 T. 14 R. 17W.  
NW NE SE

Total Depth. 3512.  
Comm. 10-7-38 Comp. 11-2-38  
Shot or Treated. 2000 gal acid.  
Contractor.  
Issued. 1-21-39

County Ellis.



CASING.

10" surface pipe 200'  
5 $\frac{1}{2}$ " O.D. 3505'

Elevation.

Production. Pot. 569 B.

Figures Indicate Bottom of Formations.

surface	8
sand	38
shale blue	314
shale and shells	430
sand grey and soft	540
shale red	665
sand	800
shale red	1150
shale blue and shells	1168
anhydrite	1211
shale blue	1225
shale red	1256
shale and shells	1610
salt shale and shells	1822
lime light	1862
shale blue	1868
lime light	1963
shale blue	1980
lime	2028
broken lime	2082
shale red	2094
lime light	2426
shale red	2434
lime hard	2525
shale and shells	2537
lime with shale breaks	2550
lime	2705
shale	2712
shale blue and shells	2761
shale strks	2772
lime hard	2794
shale and blue shells	2863
lime	2925
shale blue and shells	2957
shale and shells	2975
lime light	3070
shale & lime shells	3095
lime	3255
shale lime shells	3271
lime	3291
broken lime	3298
lime hard	3500
Hole cores	3505
lime	3512
oil encountered	3507-3512
Total Depth.	