

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


Company- SUNRAY OIL CORPORATION  
Farm- George No. 2

SEC. 5 T. 14 R. 17W  
C N/2 NW NE

Total Depth. 35 95  
Comm. 3-27-53 Comp. 4-9-53  
Shot or Treated.  
Contractor. Stickle Drilling Co.  
Issued. 6-20-53

County Ellis

KANSAS



Elevation. 2031 RB

Production. Pump 3/4 BO &  
Pumped off

CASING:

8 5/8 set at 1230' w/ 900 sx cement  
5 1/2 set at 3556' w/ 75 sx cement

Figures Indicate Bottom of Formations.

clay	100
shale	415
shale & shells	625
shale & sand	818
shale & shells	990
shale, shells & red bed	1232
sand & red bed	1402
red bed	1700
shale & salt	1850
lime & shale	2225
lime	2345
lime & shale	3222
lime	3269
shale & lime	3340
lime	3397
lime & shale	3418
lime	3456
lime & conglomerate	3507
lime	3555
Arbuckle lime	3560 R.T.D.
lime	3595
Total Depth	

TOPS:

Lansing	3305
Conglomerate	3536
Arbuckle	3555

DST #1: 3322-40, open 1 hr. rec.  
125' O&GCM

DST #2: 3378-97, open 1 hr. rec.  
45' muddy water