


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- LEBEN DRILLING, INC. & ARTNELL CO.
Farm- Pfeiffer No. 1

SEC. 5 T. 14 R. 17W
NW NE SW

Total Depth. 3590'
Comm. 5-14-58 Comp. 5-26-58
Shot or Treated.
Contractor. Leben Drlg.
Issued. 8-9-58

County Ellis
KANSAS



CASING:
8 5/8" 205' cem w/150 sx.
5 1/2" 3586 1/2' cem w/100 sx., 2nd stage @ 1245'
w/500 sx cem.

Elevation. 2024' KB

Production. 25 BOPD

Figures Indicate Bottom of Formations.

surface clay	30
sand	65
blue shale	205
shale	450
redbed & shale	480
shale & shells	690
sand & shale	850
shale & shells	920
shale & sand	1185
shale	1230
Anhydrite	1260
lime & shale	2300
lime & shale	2385
lime	2390
shale & lime	2515
lime & shale	3055
lime	3120
lime & shale	3345
lime	3380
lime	3545
Dolomite	3590 RTD
Total Depth	

TOPS: LOG

Heebner	3249
Toronto	3269
Lansing	3294
Base Kansas City	3484
Arbuckle	3534