


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- BIRMINGHAM-BARTLETT DRIG.  
Farm- Goetz "A" No. 1

SEC. 9 T. 14 R. 17W  
NW SE SE

Total Depth. 3548'  
Comm. 10-24-56 Comp. 11-3-56  
Shot or Treated.  
Contractor. Birmingham-Bartlett Drlg. Co.  
Issued. 12-8-56

County Ellis  
KANSAS



CASING:  
8 5/8" 180' w/165 sx cem.  
5 1/2" 3530' w/125 sx cem.

Elevation. 2017 RB

Production. 30 BOPD

Figures indicate Bottom of Formations.

shale-shells	675
snarl-shale	825
shale-red bed	1180
Anhydrite	1224
shale-shells	1360
shale	1875
shale-lime	2628
shale-shells	2835
lime-shale	3300
lime	3532RTD
lime	3548
Total Depth	

TOPS:  
Anhydrite 1180  
Heebner 3242  
Toronto 3261  
Lansing 3288  
Arbuckle 3528

DST #1, 3274-3302, open 1 hr.,  
weak blow. Rec. 35' muddy wtr.  
BHP 820#,

DST #2, 3314-21. Open 1 hr.,  
fair blow. Rec. 90' s. lt wtr. BHP  
800#

DST #3, 3326-40. Open 1 hr.  
Rec. 30' slightly OCM. BHP -0.

DST #4, 3349-62' Open 1 hr.  
Rec. 170' salt wtr. BHP 1000#

DST #5, 3372-99. Open 1 hr.  
Rec. 35' slightly OCM. BHP-0

Deepened to 3548'

Acidized w/2000 gal. after load  
back tested 3-3/4 BOPH for 6 hrs.,  
no wtr. Put on pump -